

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 42 गौतम नगर राष्ट्रवादी मंच गली 4,5,6 एवं कुष्ठ बस्ती बकरी मोहल्ला में जी.आई.
पाइप लाइन संधारण कार्य।

(As Per PWD Building SOR 01.01.2015)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	32.00	Cum
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area). including dressing and leveling of pits. In all types of soils.	82.50	Cum
3	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	50 mm dia. nominal bore	450.00	Metre
	40 mm dia. nominal bore	250.00	Metre
	25 mm dia. nominal bore	250.00	Metre
	15 mm dia. nominal bore	200.00	Metre
4	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	190.00	Cum
5	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end):		
	50 mm dia. nominal bore	7	each
	40 mm dia. nominal bore	5	each
6	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	25	each

Executive Engineer
Municipal Corporation
Bhilai


Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai