

MUNICIPAL CORPORATION BHILAI (C.G.)


NIT


य का नाम :- वार्ड-09 गौतम नगर में कृष्णा कबाड़ी से अंजी पुलिया एवं राम आशीष शाह के घर से योगेन्द्र राजपूत के घर तक आर.सी.सी. नाली एवं सी.सी. रोड का संधारण कार्य।

Pwd Building/ Road Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	9.36	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	1.17	Cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3	3.01	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	97.95	KG
5	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	25.50	Sqm
6	Carriage by mechanical transport for 5 km lead.	7.38	Cum
7	Providing and laying Cement Concrete for plain oncrete/reinforced concrete i/c form work, shuttering copmlete in as per drawings and specifications. (For Village roads) P.C.C.M.-10	6.60	Cum
8	Providing and laying Cement Concrete for plain oncrete/reinforced concrete i/c form work, shuttering copmlete in as per drawings and specifications. (For Village roads) P.C.C.M.-25	36.00	Cum

Executive Engineer
Municipal Corporation
Bhilai (C.G)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporatio
Bhilai (C.G)