

# MUNICIPAL CORPORATION BHILAI (C.G.)


## NIT

कार्य का नाम :- वार्ड-03 विनोबा नगर जैतखाम गली भूषण बांधे घर से आसाराम घर तक आर.सी.सी. नाली एवं सी.सी. रोड का संचारण कार्य।

PwD Building/ Road Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	8.32	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	1.04	Cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3	2.74	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	92.20	KG
5	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	23.10	Sqm
6	Carriage by mechanical transport for 5 km lead.	6.56	Cum
7	Providing and laying Cement Concrete for plain oncrete/reinforced concrete i/c form work, shuttering copmlete in as per drawings and specifications. (For Village roads) P.C.C.M.-10	11.10	Cum
8	Providing and laying Cement Concrete for plain oncrete/reinforced concrete i/c form work, shuttering copmlete in as per drawings and specifications. (For Village roads) P.C.C.M.-25	38.25	Cum

**Executive Engineer**  
Municipal Corporation  
Bhilai (C.G.)

  
**Asstt. Engineer**  
Municipal Corporation  
Bhilai (C.G.)

  
**Sub. Engineer**  
Municipal Corporatio  
Bhilai (C.G.)