

# MUNICIPAL CORPORATION OF BHILAI


NIT


वार्ड क्र-03 विनोबा नगर में मुख्य मार्ग से विनोबा नगर मुक्तिधाम मार्ग के दोनो ओर, रामचंद्र नर्सरी से गायत्री डिपार्टमेंटल मार्ग एवं सूर्या अपार्टमेंट से शिवाजी चौक में वृक्षरोपण कार्य।

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	100.00	Cum
2	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete. Aperture 50x50mm	720.00	Sqm
3	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	120.00	Sqm
4	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).	400.00	Cum
5	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).	100.00	Cum
6	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand Hedges like Alife, Dorenta, Tikoma etc	2000.00	Each
	Hibiscus (Flower)/ Rose	1500.00	Each
	Carpet grass (well developed)	100.00	Sqm
<b>Non Sor</b>			
1	Providing and Fixing Polypropylene mat finish frame size Length 6" height 18" fixing 3 nos of pot material of pot polypropylene, pot size Length 6" Hight 4.4"	1000.00	Each

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
2	Development of Garden etc preparation of soil base, plantation, sculpturing work, Electric Fitting, stone work providing and spreading different fertilizers, black soil and sand e/c Labour cost of all item e/c complete with details below (Labour cost extra)		
	Cycus	12.00	Each
	Vericted Champa	12.00	Each
	Fycus	12.00	Each
3	Labour charges for supervision & 3 year O&M including	200000.00	Rs.

  
**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Sub. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**