


# MUNICIPAL CORPORATION OF BHILAI


NIT


वार्ड 07 राधिका नगर में मैत्रीविहार कॉलोनी के आरक्षित ई.डब्ल्यू.एस. भूमि का तार फेंसिंग कार्य।

As Per PWD Building SOR 01.01.2015 & W.E.F. 01.01.2015

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	3.28	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	3.28	Cum
3	Structural steel work in single section including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	498.18	Kg
4	Providing and fixing in position G.I. barbed wire (93.8gram/m) to concrete/ wooden/ angle iron posts (straight or diagonal) including securing and screwing with G.I. tying wire, G.I. stapples, G.I.U-nails or steel pins etc., complete(Cost of posts, struts to be paid for separately)	733.20	Metre

  
Executive Engineer  
Municipal Corporation  
Bhilai (C.G)

  
Asstt. Engineer  
Municipal Corporation  
Bhilai (C.G)

  
Sub. Engineer  
Municipal Corporation  
Bhilai (C.G)