

11

MUNICIPAL CORPORATION BHILAI
NIT

कार्य का नाम :- वार्ड क्रमांक 31 आदर्श नगर रामउपकार तिवारी के पीछे ,आर.सी.सी.
नाली संधारण कार्य।

As Per PWD Road SOR 01.01.2015

| SN. | Details of Item | Qty. | Unit |
|-----|--|--------|------|
| 1 | Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar. | 2.00 | Cum |
| 2 | Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix | 2.00 | Cum |
| 3 | Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil. | 26.46 | Cum |
| 4 | Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size). | 2.94 | Cum |
| 5 | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 8.82 | Cum |
| 6 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars. | 617.40 | Kg |
| 7 | Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size | 72.80 | Sqm |
| 8 | Carriage by mechanical transport for 5 km lead. Earth | 30.46 | Cum |

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई