

MUNICIPAL CORPORATION BHILAI
NIT

वार्ड क्र. 37 संत रविदास नगर जमीला लाईन में आर.सी.सी. रोड संधारण कार्य ।।

As Per PWD Building/Road SOR 01.01.2015

SN.	Details of Item	Qty.	Unit
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads)P.C.C. M-10	3.2	Cum
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-25 @ Rs. 4286.00/m3	43.2	Cum
3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	2.40	Cum
4	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	2.00	Cum
5	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	24.00	Cum
6	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	2.40	Cum
7	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	9.11	Cum
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	637.56	Kg
9	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.26	Sqm
10	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	77.04	Sqm
11	Carriage by mechanical transport for 5 km lead. Earth	23.60	Cum

सहायक अभियन्ता
नगर पालिक निगम, भिलाई


उप अभियन्ता
नगर पालिक निगम, भिलाई