

17

# MUNICIPAL CORPORATION BHILAI

NIT

कार्य का नाम :- जोन 03 मदर टेरेसा नगर अंतर्गत विभिन्न स्थानों में आर.सी.सी. नाली एवं पुलिया संधारण कार्य।

As Per PWD Building SOR 01.01.2015

SN.	Details of Item	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	10.00	Cum
2	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	10.00	Cum
3	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	77.00	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	8.80	Cum
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	38.60	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	2702.00	Kg
7	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	248.00	Sqm
8	Carriage by mechanical transport for 5 km lead. Earth	97.00	Cum

सहायक अभियन्ता

नगर पालिक निगम, भिलाई

अभियन्ता

नगर पालिक निगम, भिलाई