


NAGAR PALIK NIGAM BHILAI

NIT

वार्ड क्र.-29 वृन्दानगर मराठी मोहल्ला में सीसी रोड निर्माण कार्य।

(AS PER P.W.D. ROAD S.O.R. W.E.F. 01.01.2015)

S.N	PARTICULAR	Qty	Unit
1	Excavation in Soil (by Manual Means.) Excavation for roadway in soil using including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	6.00	cum
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C. M-10	43.20	cum
3	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C. M-25	64.80	cum
4	Transportation of metal i/c loading & unloading For a lead upto 1 Km.	4.80	Cum
 SUB ENGINEER			
ASSTT.ENGINEER		SUB ENGINEER	
Nagar Palik Nigam, Bhilai		Nagar Palik Nigam, Bhilai	