

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT


कार्य का नाम :- वार्ड-04 नेहरू नगर पूर्व एवं पश्चिम में क्षतिग्रस्त पुलिया का संधारण कार्य।

Pwd Building Sor 01.01.2015

| S.No. | Description and details of work | Qty. | Unit |
|-------|---|---------|------|
| 1 | Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead. | 19.80 | Cum |
| 2 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils. | 35.64 | Cum |
| 3 | Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) | 8.94 | Cum |
| 4 | Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size | 26.40 | Sqm |
| 5 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars. | 2376.00 | KG |
| 6 | Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3 | 26.40 | Cum |
| 7 | Carriage by mechanical transport for 5 KM lead. | 55.44 | Cum |

Executive Engineer
Municipal Corporation
Bhilai (C.G)

Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporation
Bhilai (C.G)