

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 46 दुर्गा मंदिर स्कूल के पीछे नाली व सीमेंटीकरण का संधारण कार्य।

(As Per PWD Building & Road SOR 01.01.2015)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 Meter lead. In cement mortar.	13.20	Cum
2	Demolishing cement concrete including disposal of material within 50 meter lead. b) 1:4:8 or leaner mix	10.45	Cum
3	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose including dressing and leveling of pits. In all types of soil.	41.80	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 10mm nominal size)	10.45	Cum
5	Providing and fixing formwork i/c centering, shuttering, strutting, sagging, propping bracing etc. complete and including its removal at all levels. for : a) Foundations, footings; base of columns and plinth beam in any shape and size	242.00	Sqm
6	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	22.00	Sqm
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars.	1100.00	Kg
8	Carriage by mechanical transport for 5 km lead. Earth	45.82	Cum
9	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C. M-25	37.80	Cum

Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer
Municipal Corporation
Bhilai