

(2)


५.१६.


MUNICIPAL CORPORATION BHILAI
NIT

कार्य का नाम :- वार्ड क्रमांक 31 अंतर्गत एक्शन कमेटी सुंदर नगर सीमेंटीकरण एवं नाली निर्माण कार्य।

As Per PWD Building SOR 01.01.2015, Road SOR 2025

SN.	Particular	Qty.	Unit
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C. M-10 Road SOR6.3	12.50	Cum
2	Providing and laying Un-reinforced Cement Concrete without Dowel bars including formwork and expansion, contraction & longitudinal joints as per design and as per IRC-62, over a prepared base as per approved mix design and finishing to lines and grade as per Drawing for Pavement thickness less than 200mm in Low Volume Roads. With Cement concrete grade M-30 and minimum cement content @ 375 kg/cum Road SOR6.4	112.50	cum
3	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	84.00	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	10.50	Cum
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	29.00	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	2030.00	kg
7	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	280.00	sqm
8	Carriage by mechanical transport for 5 km lead. Earth	42.00	Cum


सहायक अभियंता
नगर पालिक निगम, भिलाई


उप अभियंता
नगर पालिक निगम, भिलाई