

कार्यालय, नगर पालिक निगम भिलाई, जिला-दुर्ग

निविदा सूचना

क्रमांक/लो.क.वि./जोन-2/2025/239

भिलाई, दिनांक : 08/12/2025

आयुक्त नगर पालिक निगम भिलाई की ओर से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से लोक निर्माण विभाग के भवन निर्माण एस.ओ.आर. दिनांक 01.01.2015/रोड एस.ओ.आर. दिनांक 01.06.2020, विद्युत एस.ओ. आर. 01.06.2020 एवं आयटम दर अद्यतन संशोधन के आधार पर कम/अधिक एवं आयटम दर पर निम्नलिखित कार्य हेतु निम्नानुसार दिनांक एवं समय तक मुहरबंद निविदा आमंत्रित की जाती है।

निविदा जारी करने की तिथि

— 08.12.2025

आवेदन की अंतिम तिथि

— 30.12.2025 सायं 5:30 बजे तक

निविदा प्रपत्र जमा करने की अंतिम तिथि

— 07.01.2026 सायं 5:30 बजे तक

निविदा खोले जाने की तिथि

— 08.01.2026 to till date

क्र.	कार्य का नाम	निविदा लागत (लाख)	धरोहर राशि	निविदा प्रपत्र का मूल्य	समयावधि	ठेकेदारों की श्रेणी	फार्म
1	सांसद निधि अंतर्गत वार्ड क्र 27 शास्त्री नगर अंतर्गत दुर्गा मंच धोभी घाट के पीछे एवं सूर्य बलब से मंच तक नाली निर्माण कार्य।	9.99	7500.00	750.00	90 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
2	वार्ड क्र.-24 फौजी नगर हाउसिंग बोर्ड में सार्वजनिक शौचालय एवं सेप्टिक टैंक निर्माण कार्य।	9.95	7500.00	750.00	120 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
3	सांसद निधि अंतर्गत वार्ड क्र 25 अंतर्गत दीप नगर में सीमेंटीकरण एवं नाली निर्माण कार्य।	9.02	7500.00	750.00	90 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
4	जोन क्र.02 वैशाली नगर के वार्ड क्र. 22 कुरुद में स्थित एस.एल.आर.एम. सेंटर के रिक्त भूमि में डोंग हाऊस निर्माण कार्य।	07.00	7000.00	750.00	120 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
5	सांसद निधि अंतर्गत वार्ड क्र 25 हाउसिंग बोर्ड सूर्यकुंड के पास उद्यान का सौन्दरीकरण कार्य।	05.00	5000.00	750.00	60 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
6	निगम मद अंतर्गत वार्ड क्र 26 रामनगर मुक्तिधाम में गति अवरोधक हेतु पास स्पीड ब्रेकर्स लगाने का कार्य।	2.99	3000.00	750.00	60 दिन	'द' एवं प्रवर	फार्म बी. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
7	पार्षद निधि अंतर्गत वार्ड क्र 21 कैलाश नगर में वार्ड के वर्मा के घर के सामने गली का सी सी रोड एवं नाली निर्माण कार्य।	1.71	2000.00	300.00	60 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
8	पार्षद निधि अंतर्गत वार्ड क्र. 21 कैलाश नगर में सन मेरिज पैलेस के पीछे विनोद राय गली सी सी रोड एवं नाली निर्माण कार्य।	1.71	2000.00	300.00	60 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम

नियम एवं शर्तें:-1. सशर्त निविदा स्वीकार नहीं की जावेगी। 2. निविदा स्पीड पोस्ट अथवा रजिस्टर्ड डाक से स्वीकार किये जावेंगे। 3. धरोहर राशि कार्यपालन अभियंता/जोन आयुक्त, नगर पालिक निगम, भिलाई एवं संबंधित ठेकेदार के नाम से संयुक्त एफ.डी.आर. किसी राष्ट्रीयकृत बैंक का संलग्न करना होगा प्रत्येक कार्य के लिये जीवित ठेकेदारी ई-पंजीयन, व्यवसायिक कर प्रमाण पत्र, पेन कार्ड, जी.एस.टी. प्रमाण-पत्र, जीवित बैंक सालवेंसी प्रमाण पत्र की सत्यापित प्रति लिफाफा "क" में प्रस्तुत करना है, एवं निविदा प्रपत्र दर सहित लिफाफा "ख" में प्रस्तुत करना होगा। 4. कर्मकार कल्याण उपकर अधिनियम लागू होगी। 5. सम्पूर्ण निविदा अथवा किसी भी अंश को स्वीकृत करने अथवा न करने का अधिकार निगम के पास सुरक्षित रहेगा। 6. नगर निगम की वाहनों से निर्माण कार्य हेतु पानी लेने पर देयक से 1% राशि की कटौती की जावेगी, किन्तु निगम वाहनों से जल उपलब्ध कराने हेतु बाध्य नहीं रहेगा। निगम क्षेत्र के स्ट्रॉतों से स्वयं के वाहनों से पानी लेने पर 0.5% की कटौती की जावेगी। 7. सफल निविदाकार की निविदा दर निविदा राशि के 90% से कम होने की स्थिति में अंतर की राशि की एफ.डी.आर. नियमानुसार परफार्मेंस गारंटी के रूप में सविदा के पूर्व जमा करना होगा। 8. शासन के निर्देशानुसार श्रमिकों से संबंधित कार्यों हेतु श्रमिकों का पी.एफ. कटौती किया जाना है तथा बैंको में खाता खोलकर सीधे उनके बैंक खाते में श्रमायुक्त द्वारा स्वीकृत दरों के अनुरूप प्रतिमाह राशि जमा किया जाना है। 09. शपथ पत्र। 10. प्रस्तुत दस्तावेज असत्य पाये जाने पर पंजीयन निरस्त कर, काली सूची में दर्ज करने की कार्यवही की जावेगी। 11. यदि निगम द्वारा निर्धारित निविदा प्राप्ति की अंतिम तिथि/निविदा खोलने की तिथि को किसी अपरिहार्य कारणवश अवकाश घोषित होता है तो ऐसी स्थिति में अंतिम तिथि/खोलने की तिथि आगामी कार्य दिवस को माना जायेगा। 12. किसी भी विवाद स्थिति में आयुक्त, नगर पालिक निगम, भिलाई का निर्णय अंतिम एवं मान्य होगा। 13. ऐसे व्यक्तियों को जो किसी भी तरह के लिए पहले ठेके निश्चित समय और राशि के पूरा करने में असफल हुए हों, को ठेका नहीं दिया जायेगा। 14. सभी दस्तावेज स्वयं प्रमाणित/नोटरी प्रमाणित होना अनिवार्य है। विस्तृत जानकारी कार्यालयीन समय एवं तिथि में कार्यालय नगर पालिक निगम, भिलाई जोन क्र.-02 वैशाली नगर तथा नगर पालिक निगमभिलाई की वेबसाइट www.bhilainagarnigam.com अथवा संचालनालय की वेबसाइट www.uad.cg.gov.in एवं चिप्स की वेबसाइट bhilai.urbanecg.gov.in से देखी जा सकती है।

जोन आयुक्त
जोन क्रमांक-02
नगर पालिक निगम
भिलाई

NAGAR NIGAM BHILAI

NIT

वार्ड क्र 24 फौजी नगर हाउसिंग बोर्ड में सार्वजनिक शौचालय निर्माण कार्य ।

(AS PER BUILDING SOR 01.01.2015 & ELECTRICAL 01.06.2020)

S.NO	PARTICULAR	QTY	UNIT
1	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.		
		2.80	cum
2	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead		
		13.20	cum
3	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.		
	In all types of soil		
		35.73	CUM
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.		
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		5.94	CUM
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.		
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		11.52	CUM
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:		
	Thermo-Mechanically treated bars		
		1151.50	KG
7	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
A	Foundations, footings, base of columns and plinth beam in any shape and size.		
		36.30	SQM
B	Columns, Pillars, Piers and likes- rectangular or square in shape		
		42.50	SQM
C	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)		

	FOR SLAB SUSPENDED ROOF	30.25	SQM
8	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	1.32	CUM
9	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand) Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	7.92	
		7.92	
		3.53	
	partition	19.37	CUM
10	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat of red oxide zinc chromate primer..	200.00	KG
11	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer.	6.30	sqm
12	12mm thick cement plaster of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	186.61	SQM
13	15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	99.00	SQM
14	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	285.61	SQM
15	Distemping with acrylic washable distemper to give an even shade. (On new work (Two or more coats)	99.00	SQM

16	Painting exterior surface with TEXTURED exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work		
		186.61	SQM
17	Providing and constructing brick masonry road gully chamber 50x45x60cm with well burnt modular clay bricks crushing strength not less than 35kg/cm ² in cement mortar 1:4 (1 cement : 4 coarse sand) including 500 x 450 mm precast R.C.C. horizontal grating with frame complete as per standard design.		
		10.00	No.
18	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design: 100 mm diameter S.W. pipe		
		20.00	mtr
19	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.		
	110 mm dia	20.00	
		20.00	mtr
	150 mm dia	50.00	
		50.00	mtr
20	Providing and constructing soak pit 1.20x1.20x1.20m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.		
		1	Each
21	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.		
		70.00	Sqm
22	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and --- 12 mm thick bed of cement Mortar 1:3 -----cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm		
		92.00	Sqm
23	Providing and fixing 10 litre capacity P.V.C. low level flushing cistern conforming to IS : 7231, with all fittings and fixtures complete. White		
		10.00	Each

24	Providing and fixing flexible P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 32 mm dia	4.00	Each
25	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required : White Orissa pattern W.C. pan of size 580x440 mm	8.00	Each
26	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : White pedestal type	2.00	Each
27	Providing and fixing vitreous china wash basin with C.I. brackets, 32mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required : White Size 550x450 mm	4.00	Each
28	Towel rail (600mm long x 20mm dia)	2.00	Each
29	Providing and fixing 30mm thick fibreglass reinforced plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF) / Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table - 3 of IS: 14856 : 2000, complete.	20.79	Sqm
30	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.		
	15 mm nominal outer dia .Pipes.	20.00	
		20.00	m
	25 mm nominal outer dia .Pipes.	40.00	
		40.00	m

31	Providing and placing on terrace (at all levels) polyethylene water storage tank ISI marked with cover and suitable locking arrangement and ---- holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.		
		1000.00	Ltr
32	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	25 mm dia. nominal bore	8.00	
		8.00	mtr
	15 mm dia. nominal bore	8.00	
		8.00	mtr
33	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete: 25 mm dia. nominal bore		
		20.00	mtr
34	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm nominal bore		
		2.00	No
35	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)		
		15.00	No
36	Providing and fixing white vitreous china urinal basin with waste fitting as per IS : 2556, and other couplings in C.P. brass complete:		
	Flat back half stall urinal of size 460x380x250mm	4.00	
		4.00	No



ASST ENGINEER

Nagar Palik Nigam, Bhilai



SUB ENGINEER

Nagar Palik Nigam, Bhilai



MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र 24 फौजी नगर हाउसिंग बोर्ड में सेप्टिक टैंक निर्माण कार्य।

AS PER PWD BUILDING S.O.R 01.01.2015

S.N.	I.N.	PARTICULAR	QTY	UNIT
1	1.1.1	Excavation for all types and sizes of foundations, trenches and drains or forupto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.In all types of soil	80.00	cum
2	3.1.3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	3.00	cum
4	3.2.1	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). Slab	16.08	cum
5	3.12.4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Cold twisted bar / Hot rolled deformed steel	1608.00	kg
6	2.1	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
6.A	2.1.8	Beams, lintels, cantilevers & walls	225.28	sqm
6.B	2.1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	20.00	sqm
8	11.5	Neat Cement punning.	94.00	sqm
9	20.29.3+ 20.30.3	Providing and constructing brick masonry chamber for underground pipe and bendsstandard design : Inside dimensions 600x 850 mm and 45 cm deep for pipe line with three or more inlets : + Providing and constructing brick work for extra depth beyond 45 cm of brick masonry chamber with well burnt modular clay bricks crushing strength..... cement on walls: For 600x850 mm size	2.00	each
14	1.26.1	Carriage by mechanical transport upto 5 km lead: Earth	60.00	cum
15	20.4.3	Dismantling of old S.W. pipes including breaking of joints and bed concrete stacking of useful materials near the site within 50 m lead but beyond 20m and disposal of unserviceable materials: 200 mm diameter	25.00	M
16	20.2.3	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design: 200 mm diameter S.W. pipe	25.00	M
17	20.1.3	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete : 200 mm diameter	25.00	M
18	3.1.4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		

		1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).		
			0.31	Cum
				Total
<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: center;">  ASST. ENGINEER Nagar Palik Nigam, Bhilai </div> <div style="text-align: center;">  SUB ENGINEER Nagar Palik Nigam, Bhilai </div> </div>				