

कार्यालय, नगर पालिक निगम भिलाई, जिला-दुर्ग

निविदा सूचना

क्रमांक/लो.क.वि./जोन-2/2025/239

भिलाई, दिनांक : 08/12/2025

आयुक्त नगर पालिक निगम भिलाई की ओर से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से लोक निर्माण विभाग के भवन निर्माण एस.ओ.आर. दिनांक 01.01.2015/रोड एस.ओ.आर. दिनांक 01.06.2020, विद्युत एस.ओ.आर. 01.06.2020 एवं आयटम दर अद्यतन संशोधन के आधार पर कम/अधिक एवं आयटम दर पर निम्नलिखित कार्य हेतु निम्नानुसार दिनांक एवं समय तक मुहरबंद निविदा आमंत्रित की जाती है।

निविदा जारी करने की तिथि

— 08.12.2025

आवेदन की अंतिम तिथि

— 30.12.2025 सायं 5:30 बजे तक

निविदा प्रपत्र जमा करने की अंतिम तिथि

— 07.01.2026 सायं 5:30 बजे तक

निविदा खोले जाने की तिथि

— 08.01.2026 to till date

क्र.	कार्य का नाम	निविदा लागत (लाख)	धरोहर राशि	निविदा प्रपत्र का मूल्य	समयावधि	ठेकेदारों की श्रेणी	फार्म
1	सांसद निधि अंतर्गत वार्ड क्र 27 शास्त्री नगर अंतर्गत दुर्गा मंच धोभी घाट के पीछे एवं सूर्य बलब से मंच तक नाली निर्माण कार्य।	9.99	7500.00	750.00	90 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
2	वार्ड क्र.-24 फौजी नगर हाउसिंग बोर्ड में सार्वजनिक शौचालय एवं सेप्टिक टैंक निर्माण कार्य।	9.95	7500.00	750.00	120 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
3	सांसद निधि अंतर्गत वार्ड क्र 25 अंतर्गत दीप नगर में सीमेंटीकरण एवं नाली निर्माण कार्य।	9.02	7500.00	750.00	90 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
4	जोन क्र.02 वैशाली नगर के वार्ड क्र. 22 कुरुद में स्थित एस.एल.आर.एम. सेंटर के रिक्त भूमि में डोंग हाऊस निर्माण कार्य।	07.00	7000.00	750.00	120 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
5	सांसद निधि अंतर्गत वार्ड क्र 25 हाउसिंग बोर्ड सूर्यकुंड के पास उद्यान का सौन्दरीकरण कार्य।	05.00	5000.00	750.00	60 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
6	निगम मद अंतर्गत वार्ड क्र 26 रामनगर मुक्तिधाम में गति अवरोधक हेतु पास स्पीड ब्रेकर्स लगाने का कार्य।	2.99	3000.00	750.00	60 दिन	'द' एवं प्रवर	फार्म बी. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
7	पार्षद निधि अंतर्गत वार्ड क्र 21 कैलाश नगर में वार्ड के वर्मा के घर के सामने गली का सी सी रोड एवं नाली निर्माण कार्य।	1.71	2000.00	300.00	60 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम
8	पार्षद निधि अंतर्गत वार्ड क्र. 21 कैलाश नगर में सन मेरिज पैलेस के पीछे विनोद राय गली सी सी रोड एवं नाली निर्माण कार्य।	1.71	2000.00	300.00	60 दिन	'द' एवं प्रवर	फार्म ए. एवं ए.बी. सी. सेड्यूल ऑफ आयटम

नियम एवं शर्तों:-1. सशर्त निविदा स्वीकार नहीं की जावेगी। 2. निविदा स्पीड पोस्ट अथवा रजिस्टर्ड डाक से स्वीकार किये जावेंगे। 3. धरोहर राशि कार्यपालन अभियंता/जोन आयुक्त, नगर पालिक निगम, भिलाई एवं संबंधित ठेकेदार के नाम से संयुक्त एफ.डी.आर. किसी राष्ट्रीयकृत बैंक का संलग्न करना होगा प्रत्येक कार्य के लिये जीवित ठेकेदारी ई-पंजीयन, व्यवसायिक कर प्रमाण पत्र, पेन कार्ड, जी.एस.टी. प्रमाण-पत्र, जीवित बैंक सालवेंसी प्रमाण पत्र की सत्यापित प्रति लिफाफा "क" में प्रस्तुत करना है, एवं निविदा प्रपत्र दर सहित लिफाफा "ख" में प्रस्तुत करना होगा। 4. कर्मकार कल्याण उपकर अधिनियम लागू होगी। 5. सम्पूर्ण निविदा अथवा किसी भी अंश को स्वीकृत करने अथवा न करने का अधिकार निगम के पास सुरक्षित रहेगा। 6. नगर निगम की वाहनों से निर्माण कार्य हेतु पानी लेने पर देयक से 1% राशि की कटौती की जावेगी, किन्तु निगम वाहनों से जल उपलब्ध कराने हेतु बाध्य नहीं रहेगा। निगम क्षेत्र के स्ट्रॉतों से स्वयं के वाहनों से पानी लेने पर 0.5% की कटौती की जावेगी। 7. सफल निविदाकार की निविदा दर निविदा राशि के 90% से कम होने की स्थिति में अंतर की राशि की एफ.डी.आर. नियमानुसार परफार्मेंस गारंटी के रूप में सविदा के पूर्व जमा करना होगा। 8. शासन के निर्देशानुसार श्रमिकों से संबंधित कार्यों हेतु श्रमिकों का पी.एफ. कटौती किया जाना है तथा बैंको में खाता खोलकर सीधे उनके बैंक खाते में श्रमायुक्त द्वारा स्वीकृत दरों के अनुरूप प्रतिमाह राशि जमा किया जाना है। 09. शपथ पत्र। 10. प्रस्तुत दस्तावेज असत्य पाये जाने पर पंजीयन निरस्त कर, काली सूची में दर्ज करने की कार्यवही की जावेगी। 11. यदि निगम द्वारा निर्धारित निविदा प्राप्ति की अंतिम तिथि/निविदा खोलने की तिथि को किसी अपरिहार्य कारणवश अवकाश घोषित होता है तो ऐसी स्थिति में अंतिम तिथि/खोलने की तिथि आगामी कार्य दिवस को माना जायेगा। 12. किसी भी विवाद स्थिति में आयुक्त, नगर पालिक निगम, भिलाई का निर्णय अंतिम एवं मान्य होगा। 13. ऐसे व्यक्तियों को जो किसी भी तरह के लिए पहले ठेके निश्चित समय और राशि के पूरा करने में असफल हुए हों, को ठेका नहीं दिया जायेगा। 14. सभी दस्तावेज स्वयं प्रमाणित/नोटरी प्रमाणित होना अनिवार्य है। विस्तृत जानकारी कार्यालयीन समय एवं तिथि में कार्यालय नगर पालिक निगम, भिलाई जोन क्र.-02 वैशाली नगर तथा नगर पालिक निगमभिलाई की वेबसाइट www.bhilainagarnigam.com अथवा संचालनालय की वेबसाइट www.uad.cg.gov.in एवं चिप्स की वेबसाइट bhilai.urbanecg.gov.in से देखी जा सकती है।

जोन आयुक्त
जोन क्रमांक-02
नगर पालिक निगम
भिलाई

MUNICIPAL CORPORATION OF BHILAI

NIT

जान क्र.02 वैशाली नगर के वार्ड क्र. 22 कुरुद में स्थित एस.एल.आर.
एम. सेंटर के रिक्त भूमि में डोंग हाऊस निर्माण कार्य।


As Per PWD Building SOR 01.01.2015

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.		
		0.53	CUM
2	Demolishing cement concrete including disposal of material within 50metre lead		
		1.28	CUM
3	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil		
		10.88	Cum
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		0.68	Cum
5	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
	(A) Foundations, footings, base of columns and plinth beam in any shape and size.		
		27.00	sqm
6	Providing and laying nominal mix Reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 40mm nominal size).		

		18.38	Cum
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars		
		1286.25	Kg
8	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)		
		22.50	cum
9	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)		
		225.00	sqm
10	Painting exterior surface with SMOOTH exterior emulsion paint of manufacturerd with cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work		
		225.00	sqm
11	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer. Electric resistance or induction butt welded tubes Grade-250		
		700.00	kg
12	Providing and placing in position angle iron and sturt of required size i/c bottom to be split and bent at right angle in opposite direction for required length and drilling holes up to 10 mm dia as per requirement i/c priming coat with red oxide zinc chromate primer and placing the post/strut in cement concrete block>		
		1902.00	kg

	providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete. Aperture 50x50mm		
		450.00	sqm
14	Supply and fixing of precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/-5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required		
15	Providing ISI Mark 32 mm dia G.I. (B class) riser pipe and M.S. plunger rod in 3 meter length socketed on one end as per IS: 1239 (Part I) 1990 with up to date amendments and socket as per IS: 2062/1990 up to date amendments.		
		168.00	m


ASSTT. ENGINEER
 Nagar Palik Nigam, Bhilai


SUB ENGINEER
 Nagar Palik Nigam, Bhilai