

MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- वार्ड क्र. 63 सेक्टर 06 पुलिस नियंत्रण कक्ष के सामने उद्यान सौंदर्यीकरण कार्य।

Building 302 2015 & floor 302 202

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. (In all types of soils.)	252.00	Cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	126.00	Cum
3	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Plain/ normal coloured precast interlock concrete block	1260.00	Sqm
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	10.80	Cum
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	226.80	Cum
6	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	324.00	SQM
7	Extra for painting with spray painting machine instead of paint brush: on new work	324.00	Sqm
8	Providing and planting of 3'0" to 4'0" heighted wasingtonia, filipheria/bismarkia novelist plam plants with 1 '6" x 1 '6" depth pit formation and soil preparation, (Mixing organic manure and plant's protection insecticide). Up to 4 month maintenance.	16.00	each

Asstt Engineer
Municipal Corporation
Bhilai(C.G.)

Sub Engineer
Municipal Corporation
Bhilai (C.G.)