

MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम—वार्ड क्र. 62 सेक्टर 06 के विभिन्न उद्यानों में प्रकाश व्यवस्था एवं संधारण कार्य।

(As Per PWD Building sor 2015, Electric SOR 01.06.2020 & Non sor)

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.45	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	3.00	cum
3	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	68.00	SQM
4	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	100.00	Sqm
5	Painting on new work (two or more coats) satin synthetic enamel paint to give an even shade with:	100.00	Sqm
6	Structural steel work in single section including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	100.00	kg
7	Supplying and laying following sizes one number FRLS PVC insulated/XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground at a depth not less than 40 cm and upto 90 cm including excavation, sand cushioning, protective covering and refilling the trench etc as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1). 2 x 4 sq. mm	80.00	Metre
8	Supplying, laying and fixing following size submersible cable along with GI/PVC/HDFC pipe line or laid in ground etc as per specification and IS: 694 (2010). Note: Cable should be rust proof, safe from oil / Grease and under water Chemical / abrasion Resistant. 3x2.5 sqmm	100.00	Metre
9	Supply, installation, testing and commissioning of 1-3 HP 1 phase submersible motor starter cum control wall/ floor mounted type made out of not less than 1.6 mm thick MS sheet and comprising of following panel mounting switchgears there in including connection inter-connection etc. as required. a) Phase indicating lamps with fuses and toggle switches 1 set b) 1/2/3 HP 1 phase DOL starter with over load and no volt relay 1 No c) 25 A "C" curve DPMCB 1 No d) Voltmeter 0-250 V 1 set e) Ammeter 0-10 A 1 set	1.00	Each

10	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	2.25	Cum
11	Supply Of Swaged steel tubular Pole as per IS 2713 with base plate of size 300 x 3000 x 6 mm welded at bottom ----- specified height including painting with one coat of red oxide zinc chromate primer. Designation 410 SP-26 height 9.00 metre	8.00	Each
12	Erection of STEEL TUBULAR or "H" BEAM/ ISMB pole in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation and cement concrete collar of size 0.4 metre dia and 0.50 metre height from ground level including excavation and refilling etc. as per specification of length: 7 metre to 10 metre	8	Each
13	Supplying and fixing water tight terminal box made of 1.6mm thick M.S. sheet with detachable gland plate in bottom, hinged front open able cover, rubber gasket, having 1 Nos 4way connector and 1 No SPMCB inside the box for cable connection, fixed to pole with 2 Nos clamp made from 40x3mm M.S. flat with 2 No nut bolt dully painted with 2 coat of red oxide paint and 2 coat aluminium paint complete as per specification. 30 x 20 x 15 cms	1.00	Each
14	Supplying and making end termination with brass compression gland and aluminum lugs for following size armoured aluminum conductor power cable of 1.1 KV grade as per specification. 3 X 25 sq. mm (25 mm	40.00	Each
15	Supply & fixing & cramping suitable size & all type aluminum ferule/lugs for following size 1.1 KV grade power cable core/lead pressed with high pressure cramping tool including connection to switch gear/MCCB etc as required 25 sq.mm. Item - 17.28.4	2	Each
16	Supplying and fixing G.I. pipe along with wall or pole/ support with 2 Nos MS clamps for protection of under ground cable in approved manner including bolts and nuts or metal dash fasteners complete as per specification. 32 mm dia	10	Meter
17	Painting new steel and other metallic surface with red oxide zinc chromide primer paint complete with supply of material labour etc. including preparation of surface	5.40	Sqm
18	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as per specification and IS Code 3043: 1987(R 2016)	3.00	Set
19	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, multi strand wire in the existing surface/ concealed. FRLS PVC conduit / PVC casing capping as per specification and IS: 694 (2010). 3 x 2.50 sq.mm	30.00	Sqm
20	Supplying and laying following sizes one number FRLS PVC insulated/ XLPE, PVC sheathed, unarmoured, aluminium conductor power cable of 1.1 KV grade on surface/ existing cable tray with 1 mm thick GI saddle as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1). 2 x 6 sq. mm	150.00	m
21	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Separate housing for driver etc complete as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio \geq 120 lumens /watt. 120 watt	8	EACH
22	Supplying of following 230/250 volts LED Flood light. 120 watt	8	Each

23	Supplying and laying following sizes one number FRLS PVC insulated/XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground at a depth not less than 40 cm and upto 90 cm including excavation, sand cushioning, protective covering and refilling the trench etc as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1). 2 x 16 sq. mm	20	Meter
24	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, wire in surface FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) etc as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5) 3 X 10 sq. mm in 25mm conduit	100.00	Meter
25	Backed by rich industrial experience and exposure in this domain, devotedly involved in presenting wide assortment of 25mm Artificial Grass. Captivating design Vivacious colors Beautiful pattern NON SOR	20	sqm

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई