


MUNICIPAL CORPORATION BHILAI
NIT

कार्य का नाम— वार्ड क्र. 64 सेक्टर 10 जोनल मार्केट के पीछे सीमेंटीकरण सहित नाली निर्माण कार्य।

SN.	Details of Item	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 Meter lead. In cement mortar.	7.20.	Cum
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	48.60	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	5.40	Cum
4	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	66.00	Sqm
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3	15.60	Sqm
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	468.00	Kg
7	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads P.C.C. M-25	5.25	cum
8	Carriage by mechanical transport for 5 km lead. Earth	20.00	Cum

Asstt. Engineer
Municipal Corporation
Bhilai(C.G.)


Sub Engineer
Municipal Corporation
Bhilai (C.G.)