

MUNICIPAL CORPORATION OF BHILAI

NIT
वार्ड-07 राधिका नगर आकृति हाईटस के पास बस स्टाप निर्माण कार्य।

As Per PWD Building SOR 01.01.2015

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	2.25	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	2.03	Cum
3	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	1.20	Cum
4	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.35	Cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	108.00	Kg
6	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	10.50	Sqm
7	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete. SS Grade 304	1052.73	Kg

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
8	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	3.51	Cum
9	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. Size 600x600mm	20.25	Sqm

Executive Engineer
Municipal Corporation
Bhilai (C.G)

Asstt. Engineer
Municipal Corporation
Bhilai (C.G)

Sub. Engineer
Municipal Corporation
Bhilai (C.G)