

कार्यालय, नगर पालिक निगम भिलाई, जिला-दुर्ग
निविदा सूचना

क्रमांक/लो.क.वि./जोन-2/2026/2825

भिलाई, दिनांक 12-03-2026

आयुक्त नगर पालिक निगम भिलाई की ओर से एकीकृत पंजीयन प्रणाली अंतर्गत सहाय श्रेणी में पंजीकृत ठेकेदारों से लोक निर्माण विभाग के भवन निर्माण एस.ओ.आर. दिनांक 01.01.2015/रोड एस.ओ.आर. दिनांक 01.06.2020, विस्तृत एस.ओ.आर. 01.06.2020 एवं अद्यतन संशोधन के आधार पर कम/अधिक एवं आयटम दर पर निम्नलिखित कार्य हेतु निम्नानुसार दिनांक एवं समय तक मुहरबंद निविदा आमंत्रित की जाती है।

1 निविदा जारी करने की तिथि - 12.03.2026	2 आवेदन की अंतिम तिथि - 02.04.2026 सायं 5:30 बजे तक
3 निविदा प्रपत्र जमा करने की अंतिम तिथि - 09.04.2026 सायं 5:30 बजे तक	4 निविदा खोले जाने की तिथि - 10.04.2026 to till date

क्र.	कार्य का विवरण	अनुमानित लागत (लाख में)	धरोहर राशि	निविदा प्रपत्र का मूल्य	समयावधि
1	क्रियायक निधि अंतर्गत वार्ड-28 राम नगर शुभेच्छाम तालाब के पास सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
2	क्रियायक निधि अंतर्गत वार्ड क्र.-23 धारोदारा नगर जैतखाम के पास सतोन किराना दुकान के पास सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
3	क्रियायक निधि अंतर्गत वार्ड क्र. 24 हाउसिंग बोर्ड औद्योगिक क्षेत्र में निर्मित सार्वजनिक शिथान सदन का सभारण कार्य।	05.00	5000.00	750.00	90 दिन
4	क्रियायक निधि अंतर्गत वार्ड क्र. 24 फौजी नगर में सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
5	क्रियायक निधि अंतर्गत वार्ड क्र. 26 राम नगर के विभिन्न स्थानों में स्ट्रीट लाईट लगाने का कार्य।	4.00	4000.00	750.00	60 दिन
6	क्रियायक निधि अंतर्गत वार्ड क्र. 20 वैशाली नगर के विभिन्न स्थानों में स्ट्रीट लाईट लगाने का कार्य।	4.00	4000.00	750.00	60 दिन
7	क्रियायक निधि अंतर्गत वार्ड क्र. 20 खण्डेलवाल भवन के सामने सार्वजनिक भवन का पुताई व सभारण कार्य।	3.20	3500.00	750.00	60 दिन
8	क्रियायक निधि अंतर्गत वार्ड क्र. 20 वैशाली नगर के लोकानग में स्थित 02 सार्वजनिक सामुदायिक भवन का सभारण व पुताई कार्य।	03.00	3000.00	750.00	60 दिन
9	क्रियायक निधि अंतर्गत वार्ड क्र. 29 शिव मंदिर के पास सार्वजनिक डोम रोड एव चौक का सौन्दर्यीकरण कार्य।	03.00	3000.00	750.00	60 दिन
10	क्रियायक निधि अंतर्गत वार्ड-29 वृदा नगर दुर्गा मंदिर के पास सार्वजनिक स्थान पर पेंडर ब्लाक लगाने का कार्य	03.00	3000.00	750.00	60 दिन
11	क्रियायक निधि अंतर्गत वार्ड-24 हाउसिंग बोर्ड औद्योगिक क्षेत्र के जया प्रिटर के पीछे सार्वजनिक चबूतरा निर्माण कार्य।	02.00	2000.00	300.00	60 दिन
12	क्रियायक निधि अंतर्गत वार्ड-25 जवाहर नगर के मन्किम्मा मंदिर के पास सार्वजनिक नवीन भवन निर्माण कार्य।	02.00	2000.00	300.00	90 दिन
13	क्रियायक निधि अंतर्गत वार्ड क्र. 15 प्रजापति भवन के पास सार्वजनिक भवन का रंगाई व पुताई कार्य।	2.00	2000.00	300.00	60 दिन

उपरोक्त निर्माण कार्यों की निविदा की सामान्य शर्तें, धरोहर राशि, विस्तृत निविदा विज्ञप्ति, निविदा दस्तावेज व अन्य जानकारी कार्यालयीन अवधि में कार्यालय से प्राप्त की जा सकती है। साथ ही यह जानकारी नगर पालिक निगम भिलाई की वेबसाईट www.bhilainagarnigam.com अथवा संचालनालय की वेबसाईट www.uad.cg.gov.in एवं विपस की वेबसाईट www.eproc.cgstate.gov.in और bhilai.urbanecg.gov.in से देखी जा सकती है।


 जॉन क्रमांक-02
 नगर पालिक निगम
 भिलाई

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 20 खंडेलवाल भवन के सामने सार्वजनिक भवन का पुताई व संधारण कार्य।

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Dismantling lime/ cement plaster or skirting at any height raking out joints and cleaning the surface for plaster including disposal of rubbish within 50 metres lead.		
		101.52	Sqm
2	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)		
		56.00	Sqm
3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)		
		71.52	Sqm
4	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)		
		2.72	Cum
6	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.		
		84.00	Kg
7	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. Size 600x600mm		
		36.00	Sqm
8	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm		
		18.00	Sqm
9	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm		
		24.00	Sqm

[Handwritten Signature]

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
10	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.		
		358.80	Sqm
11	Painting exterior surface with TEXTURED exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:		
		358.80	Sqm
12	Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. On new work (two or more coats)		
		152.32	Sqm
13	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint		
		130.20	Sqm
14	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 50 mm Thick		
		64.00	Sqm
	NON SOR		
15	Wall Art Painting work on plain surface including material and labour cost		
		133.20	Sqm
	ASSTT.ENGINEER	SUB ENGINEER	
	Nagar Palik Nigam, Bhilai	Nagar Palik Nigam, Bhilai	