

कार्यालय, नगर पालिक निगम भिलाई, जिला-दुर्ग
निविदा सूचना

क्रमांक/लो.क.वि./जोन-2/2026/2825

भिलाई, दिनांक: 12-03-2026

आयुक्त नगर पालिक निगम भिलाई की ओर से एकीकृत पंजीयन प्रणाली अंतर्गत सहाय श्रेणी में पंजीकृत ठेकेदारों से लोक निर्माण विभाग के भवन निर्माण एस.ओ.आर. दिनांक 01.01.2015/रोड एस.ओ.आर. दिनांक 01.06.2020, विस्तृत एस.ओ.आर. 01.06.2020 एवं अद्यतन संशोधन के आधार पर कम/अधिक एवं आयटम दर पर निम्नलिखित कार्य हेतु निम्नानुसार दिनांक एवं समय तक मुहरबंद निविदा आमंत्रित की जाती है।

1 निविदा जारी करने की तिथि - 12.03.2026	2 आवेदन की अंतिम तिथि - 02.04.2026 साय 5:30 बजे तक
3 निविदा प्रपत्र जमा करने की अंतिम तिथि - 09.04.2026 साय 5:30 बजे तक	4 निविदा खोले जाने की तिथि - 10.04.2026 to till date

क्र.	कार्य का विवरण	अनुमानित लागत (लाख में)	धरोहर राशि	निविदा प्रपत्र का मूल्य	समयावधि
1	क्रियायक निधि अंतर्गत वार्ड-28 राम नगर सुवैतण्यम तालाब के पास सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
2	क्रियायक निधि अंतर्गत वार्ड क्र.-23 धारोदारा नगर जैतखाम के पास सतोन किराना दुकान के पास सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
3	क्रियायक निधि अंतर्गत वार्ड क्र. 24 हाउसिंग बोर्ड औद्योगिक क्षेत्र में निर्मित सार्वजनिक शिथान सदन का सभारण कार्य।	05.00	5000.00	750.00	90 दिन
4	क्रियायक निधि अंतर्गत वार्ड क्र. 24 फौजी नगर में सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
5	क्रियायक निधि अंतर्गत वार्ड क्र. 26 राम नगर के विभिन्न स्थानों में स्ट्रीट लाईट लगाने का कार्य।	4.00	4000.00	750.00	60 दिन
6	क्रियायक निधि अंतर्गत वार्ड क्र. 20 वैशाली नगर के विभिन्न स्थानों में स्ट्रीट लाईट लगाने का कार्य।	4.00	4000.00	750.00	60 दिन
7	क्रियायक निधि अंतर्गत वार्ड क्र. 20 खण्डेलवाल भवन के सामने सार्वजनिक भवन का पुताई व सभारण कार्य।	3.20	3500.00	750.00	60 दिन
8	क्रियायक निधि अंतर्गत वार्ड क्र. 20 वैशाली नगर के लोकायन में स्थित 02 सार्वजनिक सामुदायिक भवन का सभारण व पुताई कार्य।	03.00	3000.00	750.00	60 दिन
9	क्रियायक निधि अंतर्गत वार्ड क्र. 29 शिव मंदिर के पास सार्वजनिक डोम रोड एव चौक का सौन्दर्यीकरण कार्य।	03.00	3000.00	750.00	60 दिन
10	क्रियायक निधि अंतर्गत वार्ड-29 वृदा नगर दुर्गा मंदिर के पास सार्वजनिक स्थान पर पेदर ब्लाक लगाने का कार्य	03.00	3000.00	750.00	60 दिन
11	क्रियायक निधि अंतर्गत वार्ड-24 हाउसिंग बोर्ड औद्योगिक क्षेत्र के जया प्रिटर के पीछे सार्वजनिक चबूतरा निर्माण कार्य।	02.00	2000.00	300.00	60 दिन
12	क्रियायक निधि अंतर्गत वार्ड-25 जवाहर नगर के मन्किम्मा मंदिर के पास सार्वजनिक नवीन भवन निर्माण कार्य।	02.00	2000.00	300.00	90 दिन
13	क्रियायक निधि अंतर्गत वार्ड क्र. 15 प्रजापति भवन के पास सार्वजनिक भवन का रंगाई व पुताई कार्य।	2.00	2000.00	300.00	60 दिन

उपरोक्त निर्माण कार्यों की निविदा की सामान्य शर्तें, धरोहर राशि, विस्तृत निविदा विज्ञप्ति, निविदा दस्तावेज व अन्य जानकारी कार्यालयीन अवधि में कार्यालय से प्राप्त की जा सकती है। साथ ही यह जानकारी नगर पालिक निगम भिलाई की वेबसाईट www.bhilainagarnigam.com अथवा संचालनालय की वेबसाईट www.uad.cg.gov.in एवं विपस की वेबसाईट www.eproc.cgstate.gov.in और bhilai.urbanecg.gov.in से देखी जा सकती है।


 जॉन क्रमांक-02
 नगर पालिक निगम
 भिलाई

MUNICIPAL CORPORATION OF BHILAI

NIT



कार्य का नाम :- वार्ड-29 शिव मंदिर के पास सार्वजनिक डोमशेड एवं चौक का सौन्दर्यीकरण कार्य।

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Boring, providing and installing cast in situ single under reamed piles of specified diameter and length below pile cap in cement concrete 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size),required for boring true to vertical line etc. all complete. (Length of pile for payment shall be measured upto to the bottom of pile cap):		
		60.00	Metre
2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		2.160	Cum
3	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.		
		18537.27	Kg
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars		
		566.48	Kg
5	Supply and fixing of precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.		
		490.00	Sqm
6	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
(A)	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.		
		19.20	Sqm
7	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)		
		12.60	Cum
8	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)		

[Handwritten Signature]

[Handwritten Signature]



S.N.	PARTICULERS OF ITEMS	Quantity	UOM
		84.40	Sqm
9	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with th cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with : On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over)		
		84.40	Sqm
10	Painting on new work (two or more coats) to give an even shade with: Aluminium paint		
		382.20	Sqm
11	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.		
		60.00	Cum
12	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping andsweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks		
		600.00	Sqm
13	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		2.40	Cum
14	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.		
		15.00	Sqm
15	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.		
		24.00	Sqm
			
ASST ENGINEER		SUB ENGINEER	
Nagar Palik Nigam, Bhilai		Nagar Palik Nigam, Bhilai	