

**कार्यालय, नगर पालिक निगम भिलाई, जिला-दुर्ग**  
**निविदा सूचना**

क्रमांक/लो.क.वि./जोन-2/2026/2825

भिलाई, दिनांक: 12-03-2026

आयुक्त नगर पालिक निगम भिलाई की ओर से एकीकृत पंजीयन प्रणाली अंतर्गत सहाय श्रेणी में पंजीकृत ठेकेदारों से लोक निर्माण विभाग के भवन निर्माण एस.ओ.आर. दिनांक 01.01.2015/रोड एस.ओ.आर. दिनांक 01.06.2020, विस्तृत एस.ओ.आर. 01.06.2020 एवं अद्यतन संशोधन के आधार पर कम/अधिक एवं आयटम दर पर निम्नलिखित कार्य हेतु निम्नानुसार दिनांक एवं समय तक मुहरबंद निविदा आमंत्रित की जाती है।

- |   |  |
|---|--|
| 1 निविदा जारी करने की तिथि - 12.03.2026                               | 2 आवेदन की अंतिम तिथि - 02.04.2026 सायं 5:30 बजे तक  |
| 3 निविदा प्रपत्र जमा करने की अंतिम तिथि - 09.04.2026 सायं 5:30 बजे तक | 4 निविदा खोले जाने की तिथि - 10.04.2026 to till date |

क्र.	कार्य का विवरण	अनुमानित लागत (लाख में)	धरोहर राशि	निविदा प्रपत्र का मूल्य	समयावधि
1	क्रियायक निधि अंतर्गत वार्ड-28 राम नगर शुभेच्छाम तालाब के पास सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
2	क्रियायक निधि अंतर्गत वार्ड क्र.-23 धारोदारा नगर जैतखाम के पास सतोन किराना दुकान के पास सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
3	क्रियायक निधि अंतर्गत वार्ड क्र. 24 हाउसिंग बोर्ड औद्योगिक क्षेत्र में निर्मित सार्वजनिक शिथान सदन का सभारण कार्य।	05.00	5000.00	750.00	90 दिन
4	क्रियायक निधि अंतर्गत वार्ड क्र. 24 फौजी नगर में सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
5	क्रियायक निधि अंतर्गत वार्ड क्र. 26 राम नगर के विभिन्न स्थानों में स्ट्रीट लाईट लगाने का कार्य।	4.00	4000.00	750.00	60 दिन
6	क्रियायक निधि अंतर्गत वार्ड क्र. 20 वैशाली नगर के विभिन्न स्थानों में स्ट्रीट लाईट लगाने का कार्य।	4.00	4000.00	750.00	60 दिन
7	क्रियायक निधि अंतर्गत वार्ड क्र. 20 खण्डेलवाल भवन के सामने सार्वजनिक भवन का पुताई व सभारण कार्य।	3.20	3500.00	750.00	60 दिन
8	क्रियायक निधि अंतर्गत वार्ड क्र. 20 वैशाली नगर के लोकागन में स्थित 02 सार्वजनिक सामुदायिक भवन का सभारण व पुताई कार्य।	03.00	3000.00	750.00	60 दिन
9	क्रियायक निधि अंतर्गत वार्ड क्र. 29 शिव मंदिर के पास सार्वजनिक डोम रोड एव चौक का सौन्दर्यीकरण कार्य।	03.00	3000.00	750.00	60 दिन
10	क्रियायक निधि अंतर्गत वार्ड-29 वृदा नगर दुर्गा मंदिर के पास सार्वजनिक स्थान पर पेदर ब्लाक लगाने का कार्य	03.00	3000.00	750.00	60 दिन
11	क्रियायक निधि अंतर्गत वार्ड-24 हाउसिंग बोर्ड औद्योगिक क्षेत्र के जया प्रिटर के पीछे सार्वजनिक चबूतरा निर्माण कार्य।	02.00	2000.00	300.00	60 दिन
12	क्रियायक निधि अंतर्गत वार्ड-25 जवाहर नगर के मन्किम्मा मंदिर के पास सार्वजनिक नवीन भवन निर्माण कार्य।	02.00	2000.00	300.00	90 दिन
13	क्रियायक निधि अंतर्गत वार्ड क्र. 15 प्रजापति भवन के पास सार्वजनिक भवन का रंगाई व पुताई कार्य।	2.00	2000.00	300.00	60 दिन

उपरोक्त निर्माण कार्यों की निविदा की सामान्य शर्तें, धरोहर राशि, विस्तृत निविदा विज्ञप्ति, निविदा दस्तावेज व अन्य जानकारी कार्यालयीन अवधि में कार्यालय से प्राप्त की जा सकती है। साथ ही यह जानकारी नगर पालिक निगम भिलाई की वेबसाईट [www.bhilainagarnigam.com](http://www.bhilainagarnigam.com) अथवा संचालनालय की वेबसाईट [www.uad.cg.gov.in](http://www.uad.cg.gov.in) एवं विपस की वेबसाईट [www.eproc.cgstate.gov.in](http://www.eproc.cgstate.gov.in) और [bhilai.urbanecg.gov.in](http://bhilai.urbanecg.gov.in) से देखी जा सकती है।

  
 जॉन क्रमांक-02  
 नगर पालिक निगम  
 भिलाई

# MUNICIPAL CORPORATION OF BHILAI

## NIT

वार्ड क्र. 25 जवाहर नगर के मनिकम्मा मंदिर के पास सार्वजनिक नवीन भवन निर्माण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.07.2015)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	14.44	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.30	Cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	11.05	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars	1104.60	Kg
5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	3.46	Cum
6	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
(A)	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	18.48	Sqm
(B)	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	38.62	Sqm
(C)	Columns, Pillars, Piers and likes- rectangular or square in shape	24.24	Sqm
7	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	17.98	Cum
8	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	21.80	Sqm
9	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	3.83	Cum
10	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	40.06	Sqm
11	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)	47.40	Sqm
12	Painting new exterior surface (two or more coats) with PREMIUM TEXTURED paint as per manufacturer's specifications to give -- cleaning washing of surface etc. complete with :On new work (Two or more coats)	87.46	Sqm

  
Assistant Engineer  
Municipal Corporation  
Bhilai

  
Sub Engineer  
Municipal Corporation  
Bhilai

