

कार्यालय, नगर पालिक निगम भिलाई, जिला-दुर्ग
निविदा सूचना

क्रमांक/लो.क.वि./जोन-2/2026/2825

भिलाई, दिनांक: 12-03-2026

आयुक्त नगर पालिक निगम भिलाई की ओर से एकीकृत पंजीयन प्रणाली अंतर्गत रक्षण श्रेणी में पंजीकृत ठेकेदारों से लोक निर्माण विभाग के भवन निर्माण एस.ओ.आर. दिनांक 01.01.2015/रोड एस.ओ.आर. दिनांक 01.06.2020, विस्तृत एस.ओ.आर. 01.06.2020 एवं अद्यतन संशोधन के आधार पर कम/अधिक एवं आयटम दर पर निम्नलिखित कार्य हेतु निम्नानुसार दिनांक एवं समय तक मुहरबंद निविदा आमंत्रित की जाती है।

1 निविदा जारी करने की तिथि - 12.03.2026	2 आवेदन की अंतिम तिथि - 02.04.2026 सायं 5:30 बजे तक
3 निविदा प्रपत्र जमा करने की अंतिम तिथि - 09.04.2026 सायं 5:30 बजे तक	4 निविदा खोले जाने की तिथि - 10.04.2026 to till date

क्र.	कार्य का विवरण	अनुमानित लागत (लाख में)	धरोहर राशि	निविदा प्रपत्र का मूल्य	समयावधि
1	किषायक निधि अंतर्गत वार्ड-28 राम नगर शुभेच्छाम तालाब के पास सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
2	किषायक निधि अंतर्गत वार्ड क्र.-23 धारोदारा नगर जैतखाम के पास सतोन किराना दुकान के पास सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
3	किषायक निधि अंतर्गत वार्ड क्र. 24 हाउसिंग बोर्ड औद्योगिक क्षेत्र में निर्मित सार्वजनिक शिथान सदन का सभारण कार्य।	05.00	5000.00	750.00	90 दिन
4	किषायक निधि अंतर्गत वार्ड क्र. 24 फौजी नगर में सार्वजनिक सामुदायिक भवन निर्माण कार्य।	05.00	5000.00	750.00	120 दिन
5	किषायक निधि अंतर्गत वार्ड क्र. 26 राम नगर के विभिन्न स्थानों में स्ट्रीट लाईट लगाने का कार्य।	4.00	4000.00	750.00	60 दिन
6	किषायक निधि अंतर्गत वार्ड क्र. 20 वैशाली नगर के विभिन्न स्थानों में स्ट्रीट लाईट लगाने का कार्य।	4.00	4000.00	750.00	60 दिन
7	किषायक निधि अंतर्गत वार्ड क्र. 20 खण्डेलवाल भवन के सामने सार्वजनिक भवन का पुताई व सभारण कार्य।	3.20	3500.00	750.00	60 दिन
8	किषायक निधि अंतर्गत वार्ड क्र. 20 वैशाली नगर के लोकायन में स्थित 02 सार्वजनिक सामुदायिक भवन का सभारण व पुताई कार्य।	03.00	3000.00	750.00	60 दिन
9	किषायक निधि अंतर्गत वार्ड क्र. 29 शिव मंदिर के पास सार्वजनिक डोम रोड एव चौक का सौन्दर्यीकरण कार्य।	03.00	3000.00	750.00	60 दिन
10	किषायक निधि अंतर्गत वार्ड-29 वृदा नगर दुर्गा मंदिर के पास सार्वजनिक स्थान पर पेदर ब्लाक लगाने का कार्य	03.00	3000.00	750.00	60 दिन
11	किषायक निधि अंतर्गत वार्ड-24 हाउसिंग बोर्ड औद्योगिक क्षेत्र के जया प्रिटर के पीछे सार्वजनिक चबूतरा निर्माण कार्य।	02.00	2000.00	300.00	60 दिन
12	किषायक निधि अंतर्गत वार्ड-25 जवाहर नगर के मन्किम्मा मंदिर के पास सार्वजनिक नवीन भवन निर्माण कार्य।	02.00	2000.00	300.00	90 दिन
13	किषायक निधि अंतर्गत वार्ड क्र. 15 प्रजापति भवन के पास सार्वजनिक भवन का रंगाई व पुताई कार्य।	2.00	2000.00	300.00	60 दिन

उपरोक्त निर्माण कार्यों की निविदा की सामान्य शर्तें, धरोहर राशि, विस्तृत निविदा विज्ञप्ति, निविदा दस्तावेज व अन्य जानकारी कार्यालयीन अवधि में कार्यालय से प्राप्त की जा सकती है। साथ ही यह जानकारी नगर पालिक निगम भिलाई की वेबसाईट www.bhilainagarnigam.com अथवा संचालनालय की वेबसाईट www.uad.cg.gov.in एवं विपस की वेबसाईट www.eproc.cgstate.gov.in और bhilai.urbanecg.gov.in से देखी जा सकती है।


 जॉन क्रमांक-02
 नगर पालिक निगम
 भिलाई

NAGAR PALIK NIGAM BHILAI

NIT


विधायक निधि अंतर्गत वार्ड क्र.-23 घासीदास नगर जैत खाम के पास संतोष किराना दुकान के पास सार्वजनिक सामुदायिक
AS PER PWD BUILDING S.O.R 01.01.2015 & Elec. 01.06.2020

SN	PARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or forupto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.In all types of soil		
		24.78	cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		8.80	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		18.79	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415		
		1878.56	kg
5	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
5.a	Foundations, footings, base of columns and plinth beam in any shape and size.		
		30.80	sqm
5.b	Columns, Pillars, Piers and likes- rectangular or square in shape		
		32.00	sqm
5.c	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)		
		130.58	sqm
5.d	Beams, lintels, cantilevers & walls		
		39.00	sqm
6	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)		
		4.92	cum
7	super structure Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)		
		16.22	cum
8	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.		
		31.80	cum
9	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including formwork		
		0.32	sqm

[Handwritten Signature]



10	Providing and fixing steel door with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of .. all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer..	127.20	kg
11	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat of red oxide zinc chromate primer..		
12	6 mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)	64.80	kg
13	12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	81.08	sqm
14	15mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	85.20	sqm
15	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	114.00	sqm
16	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	60.32	sqm
17	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	9.60	sqm
18	Distempering with acrylic washable distemper to give an even shade: on new work.(two or more coats) qty of no 12+13	166.28	sqm
19	Painting new exterior surface (two or more coats) with PREMIUM TEXTURED paint as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats)	166.28	sqm
20	Painting on new work (two or more coats) to give an even shade with.Premium synthetic enamel paint (2nd top most approved branded quality) to give an even shade .	114.00	sqm
		21.36	sqm



ASSTT.ENGINEER
Nagar Palik Nigam, Bhilai



SUB ENGINEER
Nagar Palik Nigam, Bhilai

