

**MUNICIPAL CORPORATION OF BHILAI**  
**NIT**


वार्ड क्र. 46 मिनीमाता नगर, खुर्सीपार में सार्वजनिक सामुदायिक भवन निर्माण कार्य।

As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020

| S.N. | PARTICULARS OF ITEMS   | Quantity | UOM |
|------|--|----------|-----|
| 1    | Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.   | 10.56    | Cum |
| 2    | Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.  | 1.70     | Cum |
| 3    | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.  | 28.58    | Cum |
| 4    | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.<br>1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).   | 3.40     | Cum |
| 5    | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.<br>1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).  | 16.832   | Cum |
| 6    | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars   | 1683.20  | Kg  |
| 7    | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:  |          |     |
| (A)  | Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.   | 24.12    | Sqm |
| (B)  | Columns, Pillars, Piers and likes- rectangular or square in shape  | 26.40    | Sqm |
| (C)  | Beams, lintels, cantilevers & walls  | 7.04     | Sqm |
| (D)  | Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)  | 53.24    | Sqm |
| 8    | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.  | 15.00    | Cum |
| 9    | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:<br>Cement Mortar 1:6 (1 cement : 6 coarse sand)  | 1.76     | Cum |
| 10   | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)<br>Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth: | 9.834    | Cum |
| 11   | Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)  | 38.08    | Sqm |
| 12   | Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)   | 66.99    | Sqm |

| S.N. | PARTICULERS OF ITEMS  | Quantity | UOM |
|------|---|----------|-----|
| 13   | Providing and making 15mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)  | 72.00    | Sqm |
| 14   | Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.   | 202.50   | Kg  |
| 15   | Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.  | 170.25   | Kg  |
| 16   | Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.  | 64.8     | Sqm |
| 17   | Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:<br>On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) | 72.00    | Sqm |
| 18   | Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. On new work (two or more coats)   | 105.07   | Sqm |
| 19   | Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint   | 35.00    | Sqm |

**Executive Engineer**  
Municipal Corporation  
Bhilai

  
**Assistant Engineer**  
Municipal Corporation  
Bhilai

  
**Sub-Engineer**  
Municipal Corporation  
Bhilai