

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 47 न्यू खुरसीपार भिलाई काली बाड़ी में सार्वजनिक भवन का संधारण कार्य।

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar	1.20	
		1.20	
		2.40	Cum
2	Dismantling lime/ cement plaster or skirting at any height raking out joints and cleaning the surface for plaster including disposal of rubbish within 50 metres lead.	80.00	
		160.00	
		240.00	Sqm
4	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	1.20	
		1.20	Cum
5	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	1.20	
		1.20	Cum
6	Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.	2	
		2	Each
7	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	3.46	
		3.46	Cum
8	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	0.29	
		9.60	
		9.89	Cum
9	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	72.00	
		88.00	
		160.00	Sqm
10	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)		
a.	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	4.00	
		4.00	Sqm
b.	Foundations, footings, bases of columns plinth beam, curtain all in anyshape and size and all type of wall below plinth level	2.00	
		3.00	
		5.00	Sqm
11	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.29	
		0.74	
		0.18	
		1.21	Cum

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
12	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). + Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth;	0.48 0.36 0.84	Cum
13	Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	0.80 0.80	Cum
14	Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand) + Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth;	0.90 0.90	Cum
15	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	6.00 6.00 12.00	Sqm
		@28.00 Kg/Sqm	336.00 Kg
16	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	4.20 1.08 5.28	Sqm
		@30.00 Kg/Sqm	158.40 Kg
17	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	160.00 160.00	Sqm
18	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	48.00 100.00 148.00	Sqm
19	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 40 mm thick	50.00 50.00	Sqm
20	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	50.00 50.00	Sqm
21	Distemping with acrylic washable distemper to give an even shade. On new work (Two or more coats)	72.00 144.00 180.00 396.00	Sqm

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
22	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)		
		310.00	
		310.00	Sqm
23	Painting on old work (one or more coats) to give an even shade with: Satin synthetic enamel paint		
		8.40	

Executive Engineer
Municipal Corporation
Bhilai


Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai