



MUNICIPAL CORPORATION OF BHILAI
NIT

वार्ड क्र. 42 गौतम नगर पम्प हाउस से लेकर रविन्दर सिंह घर तक कुस्ट बस्ती
तेलगु मोहल्ला एवं पूर्व लाईन में पाईप लाईन विस्तारीकरण कार्य।

(As Per PWD Building SOR 01.01.2015)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	16.00	Cum
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	105.00	Cum
3	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	50 mm dia. nominal bore	400.00	Metre
	40 mm dia. nominal bore	150.00	Metre
	25 mm dia. nominal bore	150.00	Metre
	15 mm dia. nominal bore	100.00	Metre
4	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with-a lead upto 50 M. and lift upto 1.5 M.	140.00	Cum
5	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	50 mm dia. nominal bore	4	each
	40 mm dia. nominal bore	3	each
6	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	31	each


Executive Engineer
Municipal Corporation
Bhilai


Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai