

# MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड 06 जी.ई.रोड के बगल में प्रियदर्शिनी परिसर के पास सार्वजनिक पुरुष प्रसाधन कक्ष निर्माण कार्य।

As Per PWD Building Sor 01.01.2015 & Electrical Sor WEF 01.06.2020

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Boring, providing and installing cast in situ single under reamed piles of specified diameter and length below pile cap in cement concrete 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size), to carry a safe working load, excluding the cost of steel reinforcement but including the cost of boring with auger by manual means and making one bulb using suitable bulb enlarging tool by MANUAL MEANS with all instruments and arrangements required for boring true to vertical line etc. all complete. (Length of pile for payment shall be measured upto to the bottom of pile cap):	18.00	Metre
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	1.37	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.04	Cum
4	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	5.68	Cum

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	694.95	Kg
	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	2.12	Cum
	Superstructure Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	10.00	Cum
6	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	13.68	Sqm
	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	27.16	Sqm
	Columns, Pillars, Piers and likes- rectangular or square in shape	9.00	Sqm
	Beams, lintels, cantilevers & walls	5.56	Sqm
9	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	10.50	Cum
10	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 300x300mm	21.00	Sqm

UOMs:

	PARTICULARS OF ITEMS	Quantity	UOM
11	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	86.94	Sqm
12	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	21.00	Sqm
13	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	86.94	Sqm
14	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	39.00	Sqm
15	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	220.50	Kg
16	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	14.58	Kg
17	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	60.00	Sqm
18	Painting on new work (two or more coats) to give an even shade with: Premium synthetic enamel paint	21.41	Sqm

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
19	Painting top of roofs with bitumen of approved quality @ 17kg/10Sqm, including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete.	21.00	Sqm
20	Add For Septik tank, Sanitation work (Indian/Uropean W.C., Wash Basin, Urinal), Water tank & Electrification work Rs.	54000.00	Rs

**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

**Sub Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**