

MUNICIPAL CORPORATION OF BHILAI

NIT

कोहका काली मंदिर के पास सड़क का मुरुमीकरण (डबलू.एम.एम.) कार्य।

S.N.	PARTICULERS OF ITEMS	As Per PWD Road 01-01-2025	
		Quantity	UOM
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all leads & lifts as per relevant clauses of section 300.	636.75	Cum
2	Granular Shoulders (Construction of granular shoulder as per clause 408 at top 150mm of earthen shoulder shall be well graded mix of at least 30% of granular sub-base material of grading-III as per clause 401 and moorum/gravel or soil and combination having soaked CBR value of not less than 30%. The granular layer shall be compacted to at least 98% of mix dry density of material as determined as per IS:2720 (Part-B))	382.05	Cum

Executive Engineer
Municipal Corporation
Bhilai (C.G)

Asstt. Engineer
Municipal Corporation
Bhilai (C.G)

Sub. Engineer
Municipal Corporation
Bhilai (C.G)