


③  
**MUNICIPAL CORPORATION OF BHILAI**

**NIT**


**वार्ड क्र. 51 खुर्सीपार गेट के पास पुलिया, संधारण कार्य।**

As Per PWD Building SOR 01.01.2015

S.N.	Item Code	PARTICULERS OF ITEMS	Quantity	UOM
1	1.1.1	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix		
2	1.1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	7.00	Cum
3	3.1.3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	7.50	Cum
4	2.1.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	2.00	Cum
5	3.2.3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	27.00	Sqm
6	3.12.1	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	8.00	Cum
			800.00	Kg

  
**Executive Engineer**  
Municipal Corporation  
Bhilai

  
**Assistant Engineer**  
Municipal Corporation  
Bhilai

  
**Sub Engineer**  
Municipal Corporation  
Bhilai