


2

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

कार्य का नाम :- वूमेन फॉर ट्री योजना अंतर्गत 9 उद्यानों में पाईप लाईन बिछाने हेतु संधारण कार्य ।

AS PER PWD BUILDING S.O.R 01.01.2015			
S.N.	PARTICULAR	QTY	UNIT
1	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete: 19.7.1		
	15 mm dia. nominal bore	74.00	MT
	25 mm dia. nominal bore	20.00	MT
	32 mm dia. nominal bore	10.00	Rmt
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.1.1.1 In all types of soils.	0.18	CUM
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.	0.18	CUM
4	Structural steel work in single section including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.PANEL BOARD PROTECTION OUTER BOX 25*25*5 1MM SHEET	29.068	KG

 R