

MUNICIPAL CORPORATION BHILAI
NIT

8

कार्य का नाम :- जोन 03 क्षेत्रांतर्गत अंतर्गत विभिन्न स्थानों में वॉल्व चेंबर संधारण कार्य।

Based on PWD/SOR 2026 (Building works)			
Item No.	Particulars of item	Qty.	Unit
1	2	3	4
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	33.12	m ³
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	33.12	m ³
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	22.36	m ³
4	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). tra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	4.14	m ³
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	1589.76	kg
6	Providing & fixing of form work l/c centering, shuttering, strutting, staging, Proping bracing etc. complete & removal upto 4 m height Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	33.12	sqm

कार्यपालन अभियंता
नगर पालिक निगम, भिलाई

सहायक अभियंता
नगर पालिक निगम, भिलाई

उप अभियंता
नगर पालिक निगम, भिलाई