


OFFICE OF THE MUNICIPAL CORPORATION BHILAI

NIT

मूलभूत सुविधा अंतर्गत वार्ड 15 अंबेडकर नगर के शांति नगर के सड़क 0 से 9 तक नाली संधारण कार्य।

CG PWD BUILDING SOR 10.06.2026

S NO	Particulars of items	QNTY	UNIT
DRAIN			
1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. All complete.		
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		38.98	cum
2	Providing and fixing form work including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.		
		649.60	sqm


ASSTT.ENGINEER
Nagar Palik Nigam, Bhilai

SUB ENGINEER
Nagar Palik Nigam, Bhilai