

NAGAR PALIK NIGAM BHILAI

NIT

ESTIMATE FOR RESTORATION OF PCC WORK AT DIFERENT PORTION OF VRINDA NAGAR AREA SITUATED AT W NO 29

CG P.W.D ROAD S.O.R. 20.04.2026

S.N.	PARTICULAR	Q	U
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.		
		78.00	cum
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads		
	P.C.C. M-10	39.00	cum
3	Providing and laying Un-reinforced Cement Concrete without Dowel bars including formwork and expansion, contraction & longitudinal joints as per design and as per IRC-62, over a prepared base a per approved mix design and finising to lines and grade as per Drawing for Pavement thickness less than 200mm in Low Volume Roads. With Cement concrete grade M-30 and minimum cement content @ 375 kg/cum		
		58.50	cum

ASSTT.ENGINEER

Nagar Palik Nigam, Bhilai

SUB ENGINEER

Nagar Palik Nigam, Bhilai