

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

Name of work :-

સોર-૦૬ બિલ્ડિંગ મલકમાં એડ ઓન રિફોર્સિંગ વર્ક
(મીનર પાલ્લી)

As per Building/Elec SOR 10.6.2026 pwd Road SoR15.06.2026

Sno	Particulars	Qty	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	20.74	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	2.59	Cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:11/2:3 (1cement :11/2 coarse sand :3 graded stone aggregate 20 mm nominal size).	8.93	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:		
	Thermo-Mechanically treated bars FE 415	714.4	Kg
5	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	20.16	Sqm
6	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.	4562.77	kg

7	Supply and fixing of precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/-5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns.s of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	179.64	Sqm.
8	Extra for providing and fixing wind ties of 40x6mm flat iron section.	54.00	Rm
9	Providing and applying priming coat on steel work with red oxide/ zinc phosphate primer applied @ 0.50 lit /Sqm as per relevant code 3536:1999 (product such as Asian Zinc phosphate , Dulux Steel primer, Burger Red oxide primer) with all tools tackles and labour etc. complete for the work.	10.00	SQM
10	Providing and applying Aluminium paint minimum 2 coats in all metal surface applying @ 0.75 lit/ 10 Sqm up to required finish as per relevant I.S. code 2932: 2013 of (Product such as Asian Apcolite aluminium paint, Dulux Aluminium paint, Burger Superior Aluminium Paint) with all tools tackle and labour etc. complete for the work.	10.00	SQM
11	Providing 40x5mm iron hold fast 40cm long including fixing to frame with 10mm bolts nuts and wooden plug and embedding in Cement Concrete 1:2:4 in blocks of size 30x10x15cm.	48.00	each
12	Providing & laying 60mm thick precast interlocking concrete	198.00	Sqm.
13(pwd Road SoR 2026)	Overhead Signs Class-C Microprismatic Grade sheeting of Type XI, fixed over 2mm thick Aluminium sheet as detailed above, for over head sign	10.80	Sqm

14(ELEC SOR)	Supplying of following 230/250 volts LED Flood light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Seperate housing for driver etc complete as per specification and P.A. should be greater than 0.9. LED chip efficacy ratio ≥ 120 lumens /watt. 300 watt	6.00	each
15(ELEC SOR)	Supplying and laying following sizes one number FRLS PVC insulated/ XLPE, PVC sheathed, unarmoured, aluminium conductor power cable of 1.1 KV grade on surface/ existing cable tray with 1 mm thick GI saddle as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1).		
	2 x 10 sq. mm	150.00	m


