

NAGAR PALIK NIGAM, BHILAI

NIT

मूलभूत सुविधा अंतर्गत वार्ड क्र. 22 कुरुद के विभिन्न स्थानों में पुलिया संधारण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)

S.NO	PARTICULAR	QTY	U
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including dressing and leveling of pits. In all types of soils.	36.90	cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.69	cum
3	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	150.90	sqm
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	27.06	cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	2706.00	kg
6	Carriage by mechanical transport upto 5 km lead:	18.45	cum

ASSTT. ENGINEER

Nagar Palik Nigam, Bhilai

SUB ENGINEER

Nagar Palik Nigam, Bhilai