

NAGAR PALIK NIGAM BHILAI NIT


मूलभूत सुविधा अंतर्गत वार्ड क्रं. 25 जवाहर नगर एम.आई.जी. कालोनी के गार्डन में
नये गणेश मंच का संधारण कार्य।

As Per PWD Building SOR 10.06.2026, Electric SOR 10.06.2026

SN	PARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or forupto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.In all types of soil		
		8.64	cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		0.58	cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		0.86	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:		
	Thermo-Mechanically treated bars FE 415	86.40	kg
5	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
5.a	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.		
		11.52	sqm
5.b	Columns, Pillars, Piers and likes- rectangular or square in shape		
		19.20	sqm

6	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)munch nd beam soiling		
		1.00	cum
7	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.		
		0.72	cum
8	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including formwork		
		0.25	sqm
9	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)		
		5.00	sqm
10	Steel work in tubular (round, square or rectangular hollow tubes etc.)structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth levelconsisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers forfastening etc. complete with applying a priming coat of red oxide zinc chromate primerElectric resistance or induction butt welded tubes Grade-250		
		1000.00	KG
11	Supply and fixing of precoated galvanized iron profile sheets (size, shapeand pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/-5% total coated thickness (TCT), Zinc coating----- any pitch in horizontal/ vertical or curved surfaces excluding the costof purlins, rafters and trusses and including cutting to size and shapewherever required.		
		80.00	sqm
12	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm		
		25.00	sqm

	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		0.45	cum
14	Providing and applying Synthatic oil bound washable Distemper having VOC content less than 50gms/ lit. Minimum two coats up to final finish to give an even shade applied 1.25 kg / 10Sqm as per relevant I.S. Code 428:2000 (product such as Asian Tractor synthatic distemper , Berger Bison Lite , Dulux Magik , Birla Opus Style super smart) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work.		
		200.00	sqm
15	Providing and applying priming coat on steel work with red oxide/ zinc phosphate primer applied @ 0.50 lit /Sqm as per relevant code 3536:1999 (product such as Asian Zinc phosphate , Dulux Steel primer, Burger Red oxide primer) with all tools tackles and labour etc. complete for the work.		
		200.00	sqm


ASSTT. ENGINEER

Nagar Palik Nigam, Bhilai


SUB ENGINEER

Nagar Palik Nigam, Bhilai