

N.I.T.


क्र. 47 टासपोर्ट नगर रोड में राहुल मैती के घर के पास नाला संधारण कार्य।

As Per PWD ROAD SOR 20.04.2026

S.N	Item Code	PARTICULERS OF ITEMS	No	L	B	H/D	QTY.	UOM
1	3.2(i)	construction of RCCopen drain 1.0m x1 1.0m insid dimension lined with 150 mm thick RCC M -20 Wall, 150 mm thick (CC) M-20 Foundation over 100 mm thick (Av) leveling course in PCC M-15 including excavastion, dressing of side and bottom provision of HYSD reinforcement consisting 10 mm dia vertical bar @150 mm c/c(L=1400mm)including cutting bending and winding wire ,placing in position ,providing shuttering and concreting by using concrete mixer ,compacting by vibration etc complete as per drawings and technical specification.						
			1	36.00			36.00	Meter

कार्यपालन अभियंता
नगर पालिक निगम भिलाई

सहायक अभियंता
नगर पालिक निगम भिलाई


 उप अभियंता
 नगर पालिक निगम भिलाई