

MUNICIPAL CORPORATION OF BHILAI


कार्य का नाम :- वार्ड क्र. 51 खुर्सीपार चन्द्रमा चौक के पास सार्वजनिक उद्यान में पेवर ब्लॉक लगाने कार्य।

N.I.T.

S.NO	Item Code	PARTICULAR	NO	L	B	H/d	QTY	UNIT
1	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in epth consolidating each deposited layer by amming and watering, including dressing etc. complete.						
			1	130.00	2.00	0.10	26.00	
							26.00	cum
2	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.						
	1.1.1	In all types of soils.	1	130.00	2.00	0.15	39.00	
							39.00	Cum
3	12.65	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm						
	12.65.2	Pigment Coloured (rubber mould) precast interlock concrete blocks	1	130.00	2.00		260.00	
							260.00	sqm
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.						
	3.1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	2	130.00	0.15	0.10	3.90	
							3.90	sqm
5	1.26	Carriage by mechanical transport upto 5 km lead:						
	1.26.1	Earth					20.00	
							20.00	cum


Executive Engineer
Municipal Corporation
Bhilai


Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai