




MUNICIPAL CORPORATION OF BHILAI
N.I.T.

वार्ड क्र. 51 खुर्सीपार रोड भाला बस्ती का नगरपालिका के पास सार्वजनिक भाली निर्माण कार्य।
(As per P.W.D BUILDING S.O.R. W.E.F. 10.06.2026)

S.N.	Item Code	PARTICULAR	NO	L	B	H/d	Qty.	Unit
1	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.						
	16.3.3	In cement mortar.						
2	16.42	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	2	100.00	0.20	0.30	12.00	cum
3	16.43	Demolishing cement concrete including disposal of material within 50metre lead.	1	5.00	2.00	0.15	1.50	cum
	16.43.2	1:3:6 or richer mix						
4	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	1	5.00	2.00	0.10	1.00	cum
	1.1.1	In all types of soils.						
5	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.	1	100.00	0.90	0.40	36.00	cum
	3.1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).						
	3.1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1	100.00	0.90	0.10	9.00	cum
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. (Note :Excess/ less cement used as per design mix is payable/ recoverable separately)	2	5.00	1.00	0.10	1.00	cum
	3.2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1	100.00	0.70	0.10	7.00	
			2	100.00	0.15	0.40	12.00	
			1	5.00	0.70	0.15	0.53	
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending etc. complete as per drawing including cost of binding wire. All complete.					19.53	cum
	3.12.1	Thermo-Mechanically treated bars FE 415						
8	2.1	Providing and fixing form work including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		50.00			976.25	kg.
	2.1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	2	100.00		0.50	100.00	
			2	100.00		0.40	80.00	
			1	5.00		0.40	2.00	
			1	12.00		0.15	1.80	
							183.80	sqm


Executive Engineer
Municipal Corporation
Bhilai


Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai