

# MUNICIPAL CORPORATION OF BHILAI

N.I.T.


वार्ड क्र. 43 बापू नगर में अम्बेडकर गार्डन के समीप एवं शारकीय अस्पताल के समीप सीमेंटीकरण कार्य।

(As Per PWD Road SOR 15.06.2026)

| S.N. | Item Code | PARTICULARS OF ITEMS                                                                                                                                                                                                                                                                                                                                                                                           | No | L      | B    | H/D            | Quantity      | UOM        |
|------|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|--------|------|----------------|---------------|------------|
| 1    | 6.3       | Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications ( For Village roads )                                                                                                                                                                                                                                    |    |        |      |                |               |            |
|      | (i)       | P.C.C. M-10                                                                                                                                                                                                                                                                                                                                                                                                    |    |        |      |                |               |            |
|      |           |                                                                                                                                                                                                                                                                                                                                                                                                                | 1  | 100.00 | 4.05 | 0.10           | 40.50         |            |
|      |           |                                                                                                                                                                                                                                                                                                                                                                                                                | 1  | 75.00  | 4.05 | 0.10           | 30.38         |            |
|      |           |                                                                                                                                                                                                                                                                                                                                                                                                                |    |        |      | <b>G.Total</b> | <b>70.88</b>  | <b>Cum</b> |
| 2    | 6.4       | Providing and laying Un-reinforced Cement Concrete without Dowel bars including formwork and expansion, contraction & longitudinal joints as per design and as per IRC-62, over a prepared base as per approved mix design and finishing to lines and grade as per Drawing for Pavement thickness less than 200mm in Low Volume Roads. With Cement concrete grade M-30 and minimum cement content @ 375 kg/cum |    |        |      |                |               |            |
|      |           |                                                                                                                                                                                                                                                                                                                                                                                                                | 1  | 100.00 | 4.00 | 0.15           | 60.00         |            |
|      |           |                                                                                                                                                                                                                                                                                                                                                                                                                | 1  | 75.00  | 4.00 | 0.15           | 45.00         |            |
|      |           |                                                                                                                                                                                                                                                                                                                                                                                                                |    |        |      | <b>G.Total</b> | <b>105.00</b> | <b>Cum</b> |
| 3    | 3.2       | Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all leads & lifts as per relevant clauses of section 300                                                                                                                                                           |    |        |      |                |               |            |
|      |           |                                                                                                                                                                                                                                                                                                                                                                                                                | 1  | 55.00  | 4.00 | 0.20           | 44.00         |            |
|      |           |                                                                                                                                                                                                                                                                                                                                                                                                                |    |        |      | <b>G.Total</b> | <b>44.00</b>  | <b>Cum</b> |

  
Executive Engineer  
Municipal Corporation  
Bhilai

  
Assistant Engineer  
Municipal Corporation  
Bhilai

  
Sub Engineer  
Municipal Corporation  
Bhilai