

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड-17 नेहरू भवन प्रेस क्लब प्रथम तल छत का संधारण कार्य।

As Per Building SOR 10.06.2026

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.	100.00	Kg
2	Providing post water proofing treatment against dampness & Seepage in roof, terraces, sunken floor of toilets with reinforced acrylic breathable (polymer content 35%, elongation at break at > 100%) coating consisting of following operations: i) Removing loose material and cleaning the surface. ii) Priming in one coat with water based acrylic emulsion. iii) Three coats with reinforced acrylic breathable polymer.	399.00	Sqm
3	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement	360.00	Sqm
4	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	150.00	Kg
5	Add 5% For Electrification & Sanitation & Water Supply Work	14847.00	Kg


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)

Sub. Engineer
Municipal Corporation
Bhilai (C.G)