

MUNICIPAL CORPORATION OF BHILAI

NIT

जोन-01 नेहरू नगर अंतर्गत वर्षा ऋतु में विभिन्न वार्डों के क्षतिग्रस्त मार्गों का संधारण कार्य।

As Per PWD Road SOR 20.04.2026

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300	108.00	Cum
2	Granular Shoulders (Construction of granular shoulder as per clause 408 at top 150mm of earthen shoulder shall be well graded mix of at least 30% of granular sub-base material of grading-III as per clause 401 and moorum/gravel or soil and combination having soaked CBR value of not less than 30%. The granular layer shall be compacted to at least 98% of mix dry density of material as determined as per IS:2720 (Part-B)	504.00	Cum
3	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)	81.00	Cum

Asstt. Engineer
Municipal Corporation
Bhilai (C.G)

Sub. Engineer
Municipal Corporation
Bhilai (C.G)