

# MUNICIPAL CORPORATION OF BHILAI

N.I.T.

वार्ड क्र. 39 स्वीपर मोहल्ला में शौचालय संधारण कार्य।

(As Per PWD Building SOR 10.06.2026 & Electric SOR 10.06.2026)


| S.N. | PARTICULERS OF ITEMS                                                                                                                                                                                                                                                                                                               | No | L    | B     | H/D             | Quantity      | UOM          |
|------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|-------|-----------------|---------------|--------------|
| 1    | Demolishing cement concrete including disposal of material within 50 metre lead.<br>1:4:8 or leaner mix                                                                                                                                                                                                                            |    |      |       |                 |               |              |
|      |                                                                                                                                                                                                                                                                                                                                    | 6  | 1.20 | 1.50  | 0.50            | 5.40          |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       | <b>G. Total</b> | <b>5.40</b>   | <b>Cum</b>   |
|      | 1:3:6 or leaner mix                                                                                                                                                                                                                                                                                                                |    |      |       |                 |               |              |
|      |                                                                                                                                                                                                                                                                                                                                    | 6  | 1.20 | 1.50  | 0.10            | 1.08          |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       | <b>G. Total</b> | <b>1.08</b>   | <b>Cum</b>   |
| 2    | Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete 100 mm diameter                                                                                                                    |    |      |       |                 |               |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       |                 | 20.00         |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       | <b>G. Total</b> | <b>20.000</b> | <b>Metre</b> |
| 3    | Providing and constructing brick masonry road gully chamber 50x45x60 cm with well burnt modular clay bricks crushing strength not less than 35kg/cm <sup>2</sup> in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450 mm precast R.C.C. horizontal grating with frame complete as per standard design.                |    |      |       |                 |               |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       |                 | 20.00         |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       | <b>G.Total</b>  | <b>20.00</b>  | <b>Each</b>  |
| 4    | Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 40 mm thick                                                                                                                                                           |    |      |       |                 |               |              |
|      |                                                                                                                                                                                                                                                                                                                                    | 1  | 5.00 | 10.00 |                 | 50.00         |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       | <b>G.Total</b>  | <b>50.00</b>  | <b>Metre</b> |
| 5    | Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design: 100 mm diameter S.W. pipe                                                                                                    |    |      |       |                 |               |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       |                 | 20.00         |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       | <b>G.Total</b>  | <b>20.00</b>  | <b>Metre</b> |
| 6    | Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.<br>In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.                                                                         |    |      |       |                 |               |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       |                 | 300.00        |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       | <b>G. Total</b> | <b>300.00</b> | <b>Kg</b>    |
| 7    | Providing and fixing steel door made of angle iron of suitable sizes with M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.                                                                                                                                        |    |      |       |                 |               |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       |                 | 100.00        |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       | <b>G. Total</b> | <b>100.00</b> | <b>Kg</b>    |
| 8    | Providing and fixing sliding shutter with M.S. sheet 1mm thick, frame and diagonal braces of 40x40x6mm angle iron, 3.0 mm thick M.S. gusset plates at junctions and corners, 25mm dia pulley, 40x40x6mm angle and T-iron guide at top and bottom respectively including applying a priming coat of red oxide zinc chromate primer. |    |      |       |                 |               |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       |                 | 60.00         |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       | <b>G. Total</b> | <b>60.00</b>  | <b>Kg</b>    |
| 9    | Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.<br>110 mm dia    |    |      |       |                 |               |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       |                 | 30.00         |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       | <b>G. Total</b> | <b>30.00</b>  | <b>M</b>     |
| 10   | Neat Cement punning.                                                                                                                                                                                                                                                                                                               |    |      |       |                 |               |              |
|      |                                                                                                                                                                                                                                                                                                                                    | 5  | 3.00 |       | 1.50            | 22.50         |              |
|      |                                                                                                                                                                                                                                                                                                                                    |    |      |       | <b>G. Total</b> | <b>22.50</b>  | <b>Sqm</b>   |

| S.N. | PARTICULERS OF ITEMS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                  |                     |                  |              |             |  |
|------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|---------------------|------------------|--------------|-------------|--|
|      | No                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | L                | B                   | H/D              | Quantity     | UOM         |  |
| 11   | Dismantling terrazzo or mosaic or glazed vitreous or patent cement or tiled flooring or dado skirting of any thickness without sub base.                                                                                                                                                                                                                                                                                                                                                                                                              |                  |                     |                  |              |             |  |
|      | 18                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 1.50             |                     | 1.20             | 32.40        |             |  |
|      | 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 4.20             |                     | 1.50             | 6.30         |             |  |
| 12   | Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.                                                                                                                                                                                                                                                                                                                                                                                              |                  |                     |                  |              |             |  |
|      | 8                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 4.20             | 0.20                | 0.40             | 2.69         |             |  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  |                     | <b>Total (A)</b> | <b>2.69</b>  | <b>Cum</b>  |  |
| 13   | Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.                                                                                                                                                                                                                                                                                                                                                                                                           |                  |                     |                  |              |             |  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  |                     |                  | 10           |             |  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  |                     | <b>G. Total</b>  | <b>10</b>    | <b>Each</b> |  |
| 14   | Providing and making 6mm thick cement plaster of mix:<br>In Cement mortar 1:3 (1 cement : 3 fine sand)                                                                                                                                                                                                                                                                                                                                                                                                                                                |                  |                     |                  |              |             |  |
|      | 10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 2.10             | 4.00                |                  | 84.00        |             |  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  |                     | <b>G. Total</b>  | <b>84.00</b> | <b>Sqm</b>  |  |
| 15   | Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:<br>In Cement Mortar 1:5 (1 cement : 5 fine sand)                                                                                                                                                                                                                                                                                                                                                                                                |                  |                     |                  |              |             |  |
|      | 10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 2.10             |                     | 3.00             | 63.00        |             |  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  |                     | <b>G. Total</b>  | <b>63.00</b> | <b>Sqm</b>  |  |
| 16   | Providing and making 12mm thick cement plaster of mix:<br>In Cement Mortar 1:4 (1 cement : 4 fine sand)                                                                                                                                                                                                                                                                                                                                                                                                                                               |                  |                     |                  |              |             |  |
|      | 10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 2.10             |                     | 3.00             | 63.00        |             |  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  |                     | <b>G. Total</b>  | <b>63.00</b> | <b>Sqm</b>  |  |
| 17   | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).                                                                                                                                                                                                                                                                                                    |                  |                     |                  |              |             |  |
|      | 6                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 1.50             | 1.20                | 0.15             | 1.62         |             |  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  |                     | <b>G. Total</b>  | <b>1.62</b>  | <b>Cum</b>  |  |
| 18   | Providing and fixing 30mm thick fibreglass reinforced plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF) / Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table - 3 of IS: 14856 : 2000, complete. |                  |                     |                  |              |             |  |
|      | 10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 0.90             |                     | 2.10             | 18.90        |             |  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  |                     | <b>G. Total</b>  | <b>18.90</b> | <b>Cum</b>  |  |
| 19   | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).                                                                                                                                                                                                                                                                                                   |                  |                     |                  |              |             |  |
|      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | $\frac{3.14}{4}$ | (2.00) <sup>2</sup> | 0.15             | 0.94         |             |  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  |                     | <b>G. Total</b>  | <b>0.94</b>  | <b>Sqm</b>  |  |
| 20   | Half brick thick brick masonry with fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in superstructure above plinth level upto plinth level:<br>Cement Mortar 1:4 (1 cement : 4 coarse sand)                                                                                                                                                                                                                                                                                                                    |                  |                     |                  |              |             |  |
|      | 4                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 3.14             | 0.75                | 1.2              | 11.30        |             |  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  |                     | <b>G.Total</b>   | <b>11.30</b> | <b>Sqm</b>  |  |
| 21   | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:<br>Cement Mortar 1:6 (1 cement : 6 coarse sand)                                                                                                                                                                                                                                                                                                                                                           |                  |                     |                  |              |             |  |
|      | 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 50.00            | 0.90                | 0.20             | 9.00         |             |  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                  |                     | <b>G. Total</b>  | <b>9.00</b>  | <b>Cum</b>  |  |

| S.N. | PARTICULARS OF ITEMS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | No   | L     | B    | H/D              | Quantity      | UOM         |
|------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------|------|------------------|---------------|-------------|
| 22   | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.<br>1 1/2:3 (1 cement : 1 1/2 coarse sand : 3 graded stone aggregate 20mm nominal size).Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 and finishing with cement plaster in Cement Mortar 1:3                                                                                                                                                                                                                             | 1    | 50.00 | 0.90 | 0.075            | 3.38          |             |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |       |      | <b>G. Total</b>  | <b>3.38</b>   | <b>Cum</b>  |
| 23   | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.                                                                                                                                                                                                                                                                                                                                                                                                                                       | 2    | 1.00  | 2.63 | 0.15             | 0.79          |             |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |       |      | <b>Total (A)</b> | <b>0.79</b>   | <b>Cum</b>  |
| 24   | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415                                                                                                                                                                                                                                                                                                                                                                                                |      |       |      |                  |               |             |
|      | @ 70.00 Kg / m <sup>3</sup>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |      |       |      |                  | 236.25        |             |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |       |      | <b>G. Total</b>  | <b>236.25</b> | <b>Kg</b>   |
| 25   | Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm                                                                                                                                                                                                                                                                                                                                                                    | 6    | 1.20  |      | 1.50             | 10.80         |             |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |       |      | <b>G. Total</b>  | <b>10.80</b>  | <b>Sqm</b>  |
| 26   | Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and --- 12 mm thick bed of cement Mortar 1:3 -----cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm                                                                                                                                                                                                                                                                                                                                                                        | 1.00 | 5.00  |      | 1.50             | 7.50          |             |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |       |      | <b>G. Total</b>  | <b>7.50</b>   | <b>Sqm</b>  |
| 27   | Providing and applying on exterior surface with PREMIUM Exterior emulsion paint of required shade to give protective and water proof finish minimum 3 coats applied @ 1.40 lit / 10Sqm up to final finish as per relevant I.S. Code 15489:2013 Type -2 Class D , C (Glossy /Semi Glossy finish ) (Product such as Asian Apex , Dulux Weather Shield Prima E900, Berger Weathercoat Antidust , Nerolac Everlas Excel , Nippon Sumo Etra, Opus True flex) inclusive of providing abro tape on edges and articleand cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work.(With 3Year Warranty.) | 10   | 3.00  |      | 3.00             | 90.00         |             |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |       |      | <b>G. Total</b>  | <b>90.00</b>  | <b>Sqm</b>  |
| 28   | Providing and fixing 10 litre capacity P.V.C. low level flushing cistern conforming to IS : 7231, with all fittings and fixtures complete.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      |       |      |                  |               |             |
|      | White                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |       |      |                  | 5             |             |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |       |      | <b>G. Total</b>  | <b>5</b>      | <b>Each</b> |
| 29   | Providing and fixing 30mm thick factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and-----<br>-- size of 19mm x 19mm for styles and 15x15mm for top & bottom rails. M.S. PVCsolvent adhesive etc. complete as per anufacturer's specification including 3 nos ISI marked stainless steel hinges of size 100x58x1.9 mm complete. (for W.C. and bathroom door shutter).                                                                                                                                                                                                                                      |      |       |      |                  |               |             |
|      | PVC door shutter                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 5    | 0.90  |      | 2.10             | 9.45          |             |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |       |      | <b>G. Total</b>  | <b>9.45</b>   | <b>Sqm</b>  |
| 30   | Providing and fixing flexible P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      |       |      |                  |               |             |
|      | 32 mm dia                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |      |       |      |                  | 10            |             |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |       |      | <b>G. Total</b>  | <b>10</b>     | <b>Each</b> |

| S.N. | PARTICULARS OF ITEMS                                                                                                                                                                                                                                                                                                                                                                                                                         | No | L    | B    | H/D | Quantity        | UOM              |
|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|------|-----|-----------------|------------------|
| 31   | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. |    |      |      |     |                 |                  |
|      | 15 mm nominal outer dia. Pipes.                                                                                                                                                                                                                                                                                                                                                                                                              |    |      |      |     | 20.00           |                  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |      |      |     | <b>G. Total</b> | <b>20.00 m</b>   |
|      | 25 mm nominal outer dia. Pipes.                                                                                                                                                                                                                                                                                                                                                                                                              |    |      |      |     | 20.00           |                  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |      |      |     | <b>G. Total</b> | <b>20.00 m</b>   |
| 32   | Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:                                                                                                                                                                                                                                                                    |    |      |      |     |                 |                  |
|      | 25 mm dia. nominal bore                                                                                                                                                                                                                                                                                                                                                                                                                      |    |      |      |     | 15.00           |                  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |      |      |     | <b>G. Total</b> | <b>15.00 Mt</b>  |
|      | 15 mm dia. nominal bore                                                                                                                                                                                                                                                                                                                                                                                                                      |    |      |      |     | 90.00           |                  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |      |      |     | <b>G. Total</b> | <b>90.00 Mt</b>  |
| 33   | Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete:                                                                                                                                                                                                                                                           |    |      |      |     |                 |                  |
|      | 25 mm dia. nominal bore                                                                                                                                                                                                                                                                                                                                                                                                                      |    |      |      |     | 70.00           |                  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |      |      |     | <b>G. Total</b> | <b>70.00 Mt</b>  |
| 34   | Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, tamping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm                                                                                        |    |      |      |     |                 |                  |
|      | Plain/ normal coloured precast interlock concrete block                                                                                                                                                                                                                                                                                                                                                                                      | 1  | 5.30 | 4.40 |     | 23.32           |                  |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                              |    |      |      |     | <b>G. Total</b> | <b>23.32 Sqm</b> |
| 35   | Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:                                                                                                                                                                                                                                                                                                                                                             |    |      |      |     | 85              |                  |
|      | Bib cock (350 grams)                                                                                                                                                                                                                                                                                                                                                                                                                         |    |      |      |     | <b>G. Total</b> | <b>85 No</b>     |

  
**Executive Engineer**  
Municipal Corporation  
Bhilai

  
**Assistant Engineer**  
Municipal Corporation  
Bhilai

  
**Sub Engineer**  
Municipal Corporation  
Bhilai