

# MUNICIPAL CORPORATION OF BHILAI

## NIT


कार्य का नाम—वार्ड कं. 70 हुडको बाल उद्यान, सुभाष गार्डन एमआईजी 170 के समीप में उद्यान का संधारण कार्य एवं वार्ड 69 एवं 70 के विभिन्न स्थानों में सूचना बोर्ड संधारण एवं निर्माण कार्य।

As Per PWD Building SOR 20.04.2026 & ELC SOR 2026

| S.N. | PARTICULARS OF ITEMS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Quantity | UOM   |
|------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|
| 1    | Supplying and laying following sizes one number FRLS PVC insulated, PVC sheathed, steel armoured, copper conductor control power cable of 1.1 KV grade in exiting PVC/ GI pipe etc as per specification and IS 694 (2010) 4 x 1.5 sq. mm                                                                                                                                                                                                                                                                                                                                                                                                         | 110      | Meter |
| 2    | Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 30.00    | sqm   |
| 3    | Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).                                                                                                                                                                                                                                                                                                                                                                                         | 1500.00  | sqm   |
| 4    | Providing and applying on exterior surface with LITE ECONOMY Exterior Emulsion paint of required shades to give protective and water proof finish minimum three coats applied @ 1.43 lit / 10Sqm up to final finish as per relevant I.S. Code 15489:2013 Type -2 Class D, C ( Glossy /Semi Glossy finish ) (Product such as Asian ACE Spark, Dulux Promise exterior smart, Nerolac Little Master, Berger Bison Lite, Nippon Superio etc) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work (With 2 Year Warranty.) | 156.00   | sqm   |
| 5    | Providing and applying renewing glossy finish Enamel paint one coats in all surface applying @ 0.75 lit/ 10 Sqm up to required finish as per relevant I.S. code 2932: 2013 of (Product such as Asian Apcolite Premium Enamel, Dulux Promise Premium Enamel, Nerolac Synthatic Enamel, Opus Prime enamel) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackle and labour etc. complete for the work.                                                                                                                                                         | 100.00   | sqm   |
| 6    | Providing and fixing M.S. structural work fabricated from standard sections, (MS rounds, angles, channels etc.) including cutting to size, drilling welding including cost of steel fasteners, clamp in RCC structural members as directed, including two coat of enamel painting over one coat of red oxide primer complete                                                                                                                                                                                                                                                                                                                     | 100.00   | kg    |
| 7    | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.(In all types of soils.)                                                                                                                                                                                                                                                                                                                                                             | 1.40     | cum   |
| 8    | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 1 coarse sand : 4 graded stone aggregate nominal size).                                                                                                                                                                                                                                                                                                                                                                                                   | 0.40     | cum   |
| 9    | Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 421.60   | kg    |

|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |        |     |
|----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-----|
| 10 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level<br>excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).                                                                                                                                                                                                                        | 2.80   | cum |
| 11 | Providing and applying satin/ matt finish Enamel paint minimum 2 coats in all surface applying @ 0.75 lit/ 10 Sqm up to required finish as per relevant I.S. code 2932: 2013 of (Product such as Asian satin Enamel, Dulux Promise Premium Enamel, Nerolac Synthatic Enamel, Opus Prime enamel) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackle and labour etc. complete for the work. | 131.40 | cum |

**Asstt. Engineer  
Municipal Corporation  
Bhilai (C.G)**

  
**Sub Engineer  
Municipal Corporation  
Bhilai (C.G)**