

MUNICIPAL CORPORATION - BHILAI

NIT

पार्षद निधि से जोन क्रमांक 03 वार्ड क्रमांक 30 प्रगति नगर में शासकीय प्राथमिक शाला के पास मिनी उद्यान निर्माण कार्य।

As per C.G PWD Building sor w.e.f- 10-06-2026, Road SORwef 15.06.26

Sno	Particulars	Qty	Unit
1	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	100.00	Sqm
2	Spreading of sludge, dump manure or/and good earth in required thickness (Cost of sludge, dump manure or/ and good earth to be paid separately).All Area	50.00	Cum
3	Tree Guard with MS Angle Iron and Steel Wire (Providing and fixing tree guard 0.60 meter square, 2.00 meter high fabricated with MS angle iron 30 x 30 x 3 mm, MS iron 25 x 3 mm at 100mm centre to centre and steel wire 3 mm dia. welded and fabricated as per design in two halves bolted together, fixed in ground with P.C.C M-10 of dimensions 150x150x200mm.)	24.00	Each
4	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).	20.00	cumec
5	Grassing with 'Doob' grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the good earth shall be paid for separately). In rows 5 cm apart in either direction	1000.00	sqm
6	Planting of Trees and their Maintenance for one Year (Planting of trees by the road side (Avenue trees) in 0.60 m dia. holes, 1 m. deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year)	23.00	Each

कार्यपालन अभियंता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई