

MUNICIPAL CORPORATION OF BHILAI

वार्ड क्र. 46 खुर्सीपार भिलाई में तारांगनी नगर में एक नग सार्वजनिक बोर खनन कार्य।
N.I.T.

(As Per PWD Building SOR 10.06.2026 & Electric SOR 10.06.2026)

S.No	Item Code	PARTICULARS OF ITEMS	No	L	B	H/D	Qty	UOM
1	21.17	Carrying out the resistivity survey by VES method using Schlumberger configuration for locating the proper spot for drilling of tube well within the selected habitation, including photography, interpretation of resistivity data and submission of report in the desired format along with resistivity readings, necessary graph and photographs. (only successful point is payable)					1	
			1				1	Point
						G. Total		
2	21.1	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground level.						
	21.1.1	All types of soil					23.00	
	21.1.1.2	125 mm dia.	1	23.00			23.00	Metre
						G. Total		
	21.1.2	Rocky strata including Boulders.					58.00	
	21.1.2.2	125 mm dia.	1	58.00			58.00	Metre
						G. Total		
3	21.5	Supplying, assembling, lowering and fixing in vertical position in bore well, ISI marked G.I. casing pipe (Plain) medium class in 4 to 7 meters length one end fitted with socket as per IS: 1239 (Part-1&Part-2) 1992 with IVth revision (Up-to-date amendments), of reputed & approved make, including required hire & labour charges, fittings & accessories, all complete, for all depths, as per direction of Engineer-in-charge.						
	21.5.2	125 mm nominal dia	1	30.00			30.00	
						G. Total		
4	21.1	Development of tube well in accordance with IS : 2800 (part I) and IS: 11189, to establish maximum rate of usable water yield without sand content (beyond permissible limit),.....laboratory,i/c disinfection of tube well,all complete, including hire & labour charges of air compressor, tools & accessories etc., all as per requirement and direction of Engineer-in-charge.						
			1	4.00			4.00	
						G. Total		
5	21.11	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for bore well of:						
	21.11.2	125 mm dia	1				1	
						G. Total		
	23.3	<u>Electrical SOR 10-04-2026</u> Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multi-stage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as per specification and IS: 694 (2010).						
	23.3.1	1.0 HP, single phase	1				1	Each

S.No	Item Code	PARTICULARS OF ITEMS	No	L	B	H/D	Qty	UOM
	23.11	Supply, installation, testing and commissioning of 1-3 HP 1 phase submersible motor starter cum control wall/ floor mounted type made out of not less than 1.6 mm thick MS sheet and comprising of following panel mounting switchgears there in including connection inter-connection etc. as per specification. a) Phase indicating lamps with fuses and toggle switches 1 set b) 1/2/3 HP 1 phase DOL starter with over load and no volt relay 1 No c) 25 A "C" curve DPMCB 1 No d) Voltmeter 0-250 V 1 set e) Ammeter 0-10 A 1 set					2	Each
		1-3 HP	2					
	23.14	Supplying, laying and fixing following size submersible cable along with GI/PVC/HDFC pipe line or laid in ground etc as per specification and IS: 694 (2010). Submersible cable should be rust proof, safe from oil / grease and under water chemical / Abrasion resistant.					30.00	
	23.14.2	3x2.5 sqmm	1	30.00			G. Total 30.00	Metre
	23.5	Supplying and fixing of following sizes 'B' class G I pipe with all necessary Tee's, bends, sockets in the suction/ delivery line including cutting and threading etc. as per specification.					27.00	
	23.5.7	25 mm dia.	1	27.00			G. Total 30.00	Metre

Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer
Municipal Corporation
Bhilai