


NAGAR PALIK NIGAM BHILAI

NIT

पार्षद निधि अंतर्गत वार्ड 28 प्रेमनगर सुभाष चौक केसरी पान ठेला के पीछे
सीसी रोड एवं नाली निर्माण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F. 10.06.2026 & ROAD S.O.R. W.E.F. 15.06.2026)

S.N.	PARTICULAR	Q	U
	DRAIN		
1	Excavation for all types and sizes of foundations, trenches and drains 0.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil		
		4.32	cum
2	Providing and laying nominal mix cement concrete with crushed form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		0.60	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		2.76	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 415		
		317.40	Kg
5	Providing and fixing formwork including entering Foundations, footings, base of columns and plinth beam in any shape and size.and all type of wall below plinth level.		
		28.80	sqm
6	Carriage by mechanical transport upto 5 km lead:		
	Earth	3.76	cum
	C.C. ROAD		
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roadsP.C.C. M-15		
		84.15	cum


ASSTT. ENGINEER
Nagar Palik Nigam, Bhilai


SUB ENGINEER
Nagar Palik Nigam, Bhilai