


NAGAR PALIK NIGAM BHILAI

NIT

पार्षद निधि अंतर्गत वार्ड 21 कैलाश नगर शेख मंजिल निवास के पास सीसी रोड एवं
नाली निर्माण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F. 10.06.2026 & ROAD S.O.R. W.E.F. 15.06.2026)

S.N.	PARTICULAR	Q	U
	DRAIN		
1	Excavation for all types and sizes of foundations, trenches and drains 0.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil		
		6.48	cum
2	Providing and laying nominal mix cement concrete with crushed form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		0.72	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		1.92	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415		
		192.00	Kg
5	Providing and fixing formwork including entering Foundations, footings, base of columns and plinth beam in any shape and size. and all type of wall below plinth level.		
		19.20	sqm
6	Carriage by mechanical transport upto 5 km lead:		
	Earth	3.89	cum
	C.C. ROAD		
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.		
		17.20	cum
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads		
		17.20	cum
		25.80	cum
3	Transportation of metal i/c loading & unloading		
	For a lead upto 1 Km.	15.48	cum
 ASSTT. ENGINEER Nagar Palik Nigam, Bhilai  SUB ENGINEER Nagar Palik Nigam, Bhilai			