

NAGAR PALIK NIGAM BHILAI

NIT

पार्षद निधि अंतर्गत वार्ड 14 शांति नगर हन्फी मजिस्ट्र के पास रोड एवं कृपाल नगर
सड़क 04 में नाली निर्माण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F. 10.06.2026 & ROAD S.O.R. W.E.F. 15.06.2026)

S.N.	PARTICULAR	Q	U
	DRAIN		
1	Excavation for all types and sizes of foundations, trenches and drains 0.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	4.32	cum
2	Providing and laying nominal mix cement concrete with crushed form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	0.60	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	2.76	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo- Mechanically treated bars FE 415	317.40	Kg
5	Providing and fixing formwork including entering Foundations, footings, base of columns and plinth beam in any shape and size. and all type of wall below plinth level.	28.80	sqm
6	Carriage by mechanical transport upto 5 km lead:		
	Earth	2.59	cum
	C.C. ROAD		
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads P.C.C. M-15	14.85	cum

ASSTT. ENGINEER

Nagar Palik Nigam, Bhilai

SUB ENGINEER

Nagar Palik Nigam, Bhilai