

MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- वार्ड क्र . 57 सेक्टर 4 राइक 8 सड़क 3 तक नाली एवं पुलिया निर्माण कार्य

S.N	Description and details of work	Qty.	unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils	278.6	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level I excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	39.8	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of form work 1:1 1/2:3 (1 cement : 1 1/2 coarse sand : 3 graded stone aggregate 20 mm nominal size).	70.4	Cum
4	Providing and placing in position reinforcement for RCC work including straightening cutting, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete Thermo-Mechanically treated bars FE 500D	7042	Kg
5	Providing and fixing form work in including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	734.9	sqm
6	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	214.3	Cum
7	Providing and fixing form work in including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	16.8	sqm
8	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of form work 1:1 1/2:3 (1 cement : 1 1/2 coarse sand : 3 graded stone aggregate 20 mm nominal size).	3.6	Cum
9	Providing and placing in position reinforcement for RCC work including straightening cutting, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete Thermo-Mechanically treated bars FE 500D	254.0	Kg

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई