

MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- वार्ड 65 सेक्टर 10 सड़क 1 नाले के किनारे सीमेंटीकरण सहित पुलिया निर्माण कार्य।

(As Per Road sor 26.04.2026)

SN.	Details of Item	Qty.	Unit
1	Excavation in Soil (by Manual Means.) Excavation for roadway in soil using including loading in tipper for carrying of cut earth to embankment site and unloading with all leads & lifts as per relevant clauses of section 300.	67.2	cum
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads P.C.C. M-10	33.60	Cum
3	Granular Sub-base as per Table:- 400-1 Construction of granular sub-base by providing graded Material, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density, complete as per clause 401.Plant mix method (with Mechanically crushed stone only) For Sub-base cum drainage layer or upper sub-base with Grading- III Material	33.60	Cum
4	Cement Concrete Pavement (Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub-base, coarse and fine aggregate conforming to IS:383, and graded as per table 600-3, mixed as per approved mix design at site, laid, spread, vibrated, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, de-bonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing as per clause 602.) With Cement concrete grade M-30 and minimum cement content @ 375 kg/cum.	50.40	Cum

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

Dringh
उप अभियन्ता
नगर पालिक निगम, भिलाई